



NVIDIA GB NVL72 System

Validation Guide

Rik Kishnah NVIDIA Confidential Oracle Labs - NVL
1122395 2025-11-28 16:00:27

Document History

VG-12022-001_v09

Version	Date	Authors	Description of Change
01	September 11, 2024	JS, SM	Initial release
02	October 3, 2024	JS, SM	<ul style="list-style-type: none"> > Modified doc type from “Application Note” to “Validation Guide” > Added Chapter 2 “Leveraging Guidelines for NVL36 Transition to NVL72” > Updated P/F criteria for L10 and L11 box-package testing > Updated test descriptions for items under L10 and L11 Reliability > Added guidelines on RMII NC-SI validation > Added guidelines for Input EDPp testing
03	November 7, 2024	JS, SM	<ul style="list-style-type: none"> > Added PDB static and dynamic load validation for L10 > Added CPU JTAG validation for L10 > Updated SPI functional validation procedures > Added timing specification for SPI
04	December 23, 2024	JS, SM	<ul style="list-style-type: none"> > Updated Section 3.4.1 for L10 level input EDPp testing > Updated Section 3.6.8 SGPIO electrical validation for SGPIO timing parameters > Updated Section 5.1.8 Rack Power EDPp > Added Chapter 6 Appendix with sections on input EDPp waveform capture using HiRes mode and input EDPp post-processing guidelines
05	March 5, 2025	JS, GP, SM	<ul style="list-style-type: none"> > Added Section 1.2.4 related to NVNetPerf Tool > Added Section 3.7 on network I/O board validation. > Added Section 3.9.4 on information for performing L10 partner diagnostics WAT > Added Table 3-12 on loopback test cables for BF-3, CX-7 and NVLink for partner diagnostics. > Updated Table 3-18. EMC Tests Summary with updated test conditions
06	April 14, 2025	JS, SM	<ul style="list-style-type: none"> > Removed line item SY.18 from Table 2-1 > Updated Section 5.1.8 “Rack Power AC Apparent Power” > Updated test conditions in Table 5-1, Table 5-2, and Table 5-3
07	July 28, 2025	GP, SM	<ul style="list-style-type: none"> > Updated this validation guide to make it common for both GB200 NVL72 and GB300 NVL72. > Updated the title to <i>NVIDIA GB NVL72 System Validation Guide</i>. > Updated Section 3.7 to cover both CX-7 and CX-8 validation.

Version	Date	Authors	Description of Change
			> Updated Table 3-12 with CX-8 Loopback cable details
08	September 10, 2025	GP, SM	Added Chapter 7 “Validation Leverage Guidance for GB300 NVL72 Systems”.
09	October 20, 2025	GP, SM	Updated system package testing information in Table 3-13 and Table 5-1

Rik Kishnah NVIDIA Confidential Oracle Labs - NVL
1122395 2025-11-28 16:00:27

Table of Contents

Chapter 1.	Introduction.....	1
1.1	Partner Validation Playbook.....	1
1.2	Partner Validation Toolset.....	1
1.2.1	NVQual.....	2
1.2.2	NVSSVT.....	2
1.2.3	NVRASTool.....	2
1.2.4	NVNetPerf Tool.....	2
1.3	Minimum Hardware Configuration for Partner Validation.....	3
1.4	Attachments.....	5
Chapter 2.	Leveraging Guidelines for NVL36 Transition to NVL72.....	6
Chapter 3.	L10 Compute Tray Hardware Validation.....	9
3.1	Mechanical.....	9
3.2	Thermal.....	10
3.2.1	Host BMC Shdn, Event Logging for THERM_OVERT_N Assertion.....	10
3.2.2	Host BMC Shdn, Event Logging for FPGA_OVERT_N Assertion.....	11
3.3	Liquid Cooling.....	11
3.3.1	Leak Detection.....	12
3.4	Power Validation.....	14
3.4.1	Input EDP Peak Testing.....	14
3.4.2	GPU Power Brake.....	15
3.4.3	Power Distribution Board Static Loads.....	16
3.4.4	Power Distribution Board Dynamic Loads.....	16
3.5	PCIe.....	17
3.5.1	PCIe Speed and Width Configuration Check.....	17
3.5.2	PCIe Link Training Steady State Machine.....	18
3.6	I/O Interface.....	19
3.6.1	CPU JTAG Scan Check from BMC.....	20
3.6.2	Dual CPU JTAG Scan Check from BMC.....	20
3.6.3	CPU JTAG Electrical Validation.....	21
3.6.4	I2C Functional Bus Scan.....	22
3.6.5	I2C Electrical Validation.....	23
3.6.6	SPI Functional Check.....	24
3.6.7	SPI Electrical Validation.....	26
3.6.8	SGPIO Electrical Validation.....	27
3.6.9	UART Functional Check.....	30
3.6.10	UART Electrical Validation.....	31
3.6.11	RMII Network Controller Sideband Interface.....	33

3.6.12	RMII NC-SI Electrical Validation	37
3.7	Networking I/O Board	41
3.7.1	CX-7 and CX-8 Mezzanine Network Card Ethernet Validation	41
3.7.2	CX-7 and CX-8 Mezzanine Network Card I/O Board InfiniBand Validation	49
3.8	BMC	52
3.8.1	BMC FRU Write	52
3.8.2	BMC Power Control (STANDBY, RUN, AUX)	53
3.9	System	54
3.9.1	System Reboot and Power Cycle Stress Testing	54
3.9.2	Wide Area Test	55
3.9.3	Reboot WAT	56
3.9.4	L10 Partner Diagnostics WAT	57
3.10	Environmental, Reliability, and Electromagnetic Compatibility	58
3.10.1	L10 Package Testing	58
3.10.2	Shock and Vibration Test	60
3.10.3	Environmental Reliability Test	62
3.10.4	Electromagnetic Compatibility	64
Chapter 4.	L10 Compute Tray System Software	67
4.1	System Software Validation Guidelines	68
Chapter 5.	L11 Server Rack Hardware Validation	70
5.1	Rack Power	70
5.1.1	Rack Power Startup and Shutdown	71
5.1.2	Rack Power Startup and Shutdown without PSC	71
5.1.3	Rack Power Load Voltage Regulators under Static Load	72
5.1.4	Rack Power Load Voltage Regulators under Dynamic Load	73
5.1.5	Rack Power Load Hot Swap PSU	74
5.1.6	Rack Power Load Hot Swap PSC	75
5.1.7	Rack Power Fault Recovery	76
5.1.8	Rack Power AC Apparent Power	77
5.1.9	Rack Power Noise	85
5.1.10	Rack Power Firmware Update	85
5.1.11	PSC Reboot Cycles	86
5.1.12	Rack Power Factor	86
5.2	L11 Environmental, Reliability	87
5.2.1	L11 Packaging	87
5.2.2	L11 Shock and Vibration Test	89
5.2.3	L11 Environmental Reliability Test	91
Chapter 6.	Appendix 1: Oscilloscope Acquisition Modes for EDPp Measurements	93
6.1	Moving Average Measurement using Oscilloscope HiRes Mode	93
6.2	Input EDPp Post-Processing Guideline	95

Rik Kishnah NVIDIA Confidential Oracle Labs - NVL
1122395 2025-11-28 16:00:27

List of Figures

Figure 3-1.	CPU JTAG Electrical Validation.....	22
Figure 3-2.	SPI Electrical Validation	26
Figure 3-3.	SGPIO Bus Overview	28
Figure 3-4.	SGPIO Timing Diagram.....	28
Figure 3-5.	UART T _{BIT} Definition.....	32
Figure 3-6.	RMII NC-SI Diagram.....	34
Figure 3-7.	RMII NC-SI DC Specifications.....	38
Figure 3-8.	RMII NC-SI AC Specifications.....	39
Figure 5-1.	L11 Power Measurement Block Diagram.....	77
Figure 5-2.	Power Whip Wiring Diagram	79
Figure 5-3.	Current Probes and Voltage Probes Setup and Power Whip.....	80
Figure 5-4.	Connected Power Cable and Current Probe Attachments Example.....	82
Figure 6-1.	Acquisition Mode.....	94
Figure 6-2.	Oscilloscope Setting 200 μ s Moving Average Example	95

List of Tables

Table 1-1.	L10 Validation Minimum Hardware Configuration	3
Table 1-2.	L11 Validation Minimum Hardware Configuration	4
Table 2-1.	2RU to 1RU Compute Tray Transition Test Items	6
Table 3-1.	Mechanical Checklist	9
Table 3-2.	PCIe Link Specification and Minimum Hardware Configuration	17
Table 3-3.	Grace CPU PCIe LTSSM	18
Table 3-4.	JTAG Timing Specification	22
Table 3-5.	SPI Timing Parameters	26
Table 3-6.	SGPIO Timing Parameters	28
Table 3-7.	UART DC Specifications	32
Table 3-8.	UART AC Specifications	32
Table 3-9.	List of FRU EEPROMs in GB200 and GB300 Bianca Compute Tray	52
Table 3-10.	Compute Tray WAT	56
Table 3-11.	Reboot WAT	56
Table 3-12.	BF-3, CX-7, CX-8, NVLink, Loopback Cable, and Test Cage	57
Table 3-13.	L10 Packaging Test Summary	58
Table 3-14.	Shock and Vibration Test Summary	60
Table 3-15.	Mechanical Shock – Half Sine (Operating)	61
Table 3-16.	Mechanical Shock – Trapezoidal (Non-operating)	61
Table 3-17.	Reliability Test Summary	62
Table 3-18.	EMC Tests Summary	65
Table 4-1.	Reference Documentation and Collateral	67
Table 4-2.	System Software Validation Example	68
Table 5-1.	L11 Packaging Test Summary	87
Table 5-2.	L11 Shock and Vibration Test Summary	89
Table 5-3.	L11 Reliability Test Summary	91
Table 6-1.	Input EDPp and Samples per Window in Sample Mode	95

Chapter 1. Introduction

This validation guide describes the tools and methodologies that NVIDIA provides to validate and test partner platforms built for the NVIDIA GB200 NVL36, GB200 NVL72, and GB300 NVL72 systems. The validation procedure and tools in this application note are provided as a reference. Partners must supplement additional qualifications that apply to their customization.

1.1 Partner Validation Playbook

The Partner Validation Playbook (PVP) provides a systematic and standardized way to validate NVIDIA data center products, aiming to improve test effectiveness, product quality, and time-to-market.

The PVP is a workbook with detailed validation items for each ES, QS, and PS release milestone. This validation guide complements the PVP and provides instructions about how to complete these validation line items.

Refer to the *GB200 NVL System Partner Validation Playbook* (NVOnline: 1115639) and the *GB300 NVL72 System Partner Validation Playbook* (NVOnline: 1128352) for the validation line items. Partners should validate each validation line item to uncover potential issues before production.

The validation guide may not be comprehensive in covering all test items outlined in the PVP. Partners should adapt the procedures outlined in this validation guide to best fit their validation process.

Partners also should report their validation status and issues using the NVOnline portal. Refer to the *NVOnline Partner Portal Guidelines* (NVOnline: 1106745) for information about the best practices on validation review requests and NVBugs submission.

1.2 Partner Validation Toolset

This section describes the toolset available for partner validation of GB200 and GB300 NVL systems. Refer to the latest *GB200 NVL72 Partner Enablement Deck* (NVOnline: 1114628) and *GB300 NVL72 Partner Enablement Deck* (NVOnline: 1124881) for the required toolkit version for each sampling milestone.

1.2.1 NVQual

The NVQual program is a software program that allows partners to qualify NVIDIA hardware in their system. Partners must run NVQual and submit the results back to NVIDIA for review as part of their validation process.

NVQual can be downloaded from the online posting *NVQual for NVIDIA Grace-Blackwell Platforms* (NVOnline: 1119931).

1.2.2 NVSSVT

NVIDIA System Software Validation Toolkit (NVSSVT) is a toolkit developed for server platforms and includes a binary that contains the system management, performance, and other validation suites. Partners must run the NVSSVT tool and submit the results along with the PVP as part of the validation process.

NVSSVT can be downloaded from the online posting *NVIDIA System Software Validation Tool (NVSSVT)* (NVOnline: 1108364).



Note: The validation line items mentioned in this application note can be validated using the NVSSVT tool.

The following procedures are for partner references only. Partners must update their test plans for their BMC software implementation, after referring to this application note.

1.2.3 NVRASTool

The NVIDIA Reliability, Availability, and Serviceability (RAS) Tool provides a unified way to test the RAS features of NVIDIA hardware. The tool provides test coverage for Out-Of-Band (OOB), In-Band hardware error, and AML software injection. NVIDIA RASTool (NVRASTool) is available on NVOnline: 1112947.



Note: The NVIDIA NVRASTool runs on a separate machine from the computer that is being tested, remotely executes the tests automatically with no user intervention, and gathers the logs.

1.2.4 NVNetPerf Tool

The NVNetPerf Tool is a performance tool that configures multiple nodes with DPU and CX cards and tests them by running workloads to stress and identify points of failure which might not be detected when testing individual DPU or CX cards. This comprehensive test reduces risks associated with system deployment. Additionally, the NVNetPerf test assesses both North-South (N-S) and East-West (E-W) network traffic, ensuring the system operates with the most optimized and up-to-date configurations and software. This test can detect configuration issues that are not detected testing individual DPU or CX Cards.

The NVNetPerf Tool and its user guide, which details the test configuration, procedure, and performance acceptance criteria, are listed in the NVNetPerf Kit (formerly DoCA Perf test) with NVOnline: 1119887.

1.3 Minimum Hardware Configuration for Partner Validation

For faster time to market, partners can start their validation process while building out their compute tray and their multi-node server rack. Partners do not need to populate the entire compute tray or entire server rack to start their validation.

The PVP highlights the minimum hardware configuration that is required to perform each validation test item. Partners can jump-start their validation at ES with the minimum hardware configuration to uncover any issues early on.

Table 1-1 explains the minimum hardware configuration at the compute tray validation. Table 1-2 explains the minimum hardware configuration for the server rack validation.

Table 1-1. L10 Validation Minimum Hardware Configuration

Minimum Hardware Configuration	Description
Core Tray	2x Bianca boards > 1x CPU per board > 2x GPUs per board Accessory boards: > HMC integrated > BMC interposer card and BMC integrated > M.2 riser card and M.2 installed > 1x Front I/O board > 1x Power distribution board (PDB)
Core Tray + GPU-Less	2x Bianca boards > 1x CPU per board > 0x GPU per board Accessory boards: > HMC integrated > BMC interposer card and BMC integrated > M.2 riser card and M.2 installed > 1x Front I/O board > 1x Power distribution board (PDB)
Core Tray + NVLink loopbacks	2x Bianca boards > 1x CPU per board > 2x GPUs per board Accessory boards:

Minimum Hardware Configuration	Description
	<ul style="list-style-type: none"> > HMC integrated > BMC interposer card and BMC integrated > M.2 riser card and M.2 installed > 1x Front I/O board > 1x Power distribution board (PDB) NVLink loopback cable installed
Core Tray + TPM + CPU only	2x Bianca boards <ul style="list-style-type: none"> > 1x CPU per board > 0x GPUs per board Accessory boards: <ul style="list-style-type: none"> > HMC integrated > BMC interposer card and BMC integrated > M.2 riser card and M.2 installed > 1x Front IO board > 1x Power distribution board (PDB) > 1x TPM module
Full Tray	All L10 BOM fully integrated
Full Tray + GPU-Less	All L10 BOM is fully integrated with exceptions any GPUs
Full Tray + NVLink loopbacks	All L10 BOM fully integrated with NVLink loopback cables installed
PDB + E-Load	Power distribution board with electronic load test equipment

Table 1-2. L11 Validation Minimum Hardware Configuration

Minimum Hardware Configuration	Description
Full Rack	Server rack with all compute trays and switch trays populated <ul style="list-style-type: none"> > Bus bar integrated > Power shelf integrated > Manifold integrated > Cables and rails integrated
Full Rack + GPU-Less	Server rack with all compute trays and switch trays populated <ul style="list-style-type: none"> > No GPUs are required in the compute trays > Bus bar integrated > Power shelf integrated > Manifold integrated > Cables and rails integrated
Rack + 1 Full Tray	Server rack with a single fully populated compute tray <ul style="list-style-type: none"> > Bus bar integrated > Power shelf integrated > Manifold integrated > Cables and rails integrated

Minimum Hardware Configuration	Description
Rack with no compute or switch tray	Server rack without any compute tray and switch tray <ul style="list-style-type: none"> > Bus bar integrated > Power shelf integrated > Manifold integrated > Cables and rails integrated
Rack + E-Loads	Server rack without any compute tray and switch tray <ul style="list-style-type: none"> > Electronic load for load testing > Bus bar integrated > Power shelf integrated > Manifold integrated > Cables and rails integrated
Rack + 1 Core Tray	Server rack with a core compute tray See Table 1-1 for core tray definition
Full Rack Packaged on Pallet	Server rack with all compute trays and switch trays populated, and packaged on pallet

1.4 Attachments

The following files are attached to this validation guide. All example code and test scripts are provided for partner reference only. Partners are responsible for modifying and developing their own test scripts. In addition, partners are responsible for ensuring the integrity and completeness of all their validation activities including, but not limited to, test scripts, test results, and test data analysis.

- > CPU JTAG Test Script
 - The “jtag_test” can be used to perform JTAG validation under Section 3.6.1 “CPU JTAG Scan Check from BMC.”
- > GB_NVL72_PVP_Validation_Leverage_Guidance.nvzip

To access the attached files, click the **Attachment** icon on the left-hand toolbar on this PDF (using Adobe Acrobat Reader or Adobe Acrobat). Select the file and use the Tool Bar options (**Open, Save**) to retrieve the documents. Files with the .nvzip extension must be renamed to .zip and then can be extracted using 7-Zip file archive software or other archive software.

Chapter 2. Leveraging Guidelines for NVL36 Transition to NVL72

Partners can leverage their previous qualification efforts when transitioning from a 2RU NVL36 configuration to a 1RU NVL72 configuration.

A subset of the validation test items must be retested on the 1RU compute tray as part of the compute tray transition. Refer to Table 2-1 for the test items that must be performed as part of the 2RU to 1RU compute tray transition. These test items cover areas of mechanical, thermal, power, high-speed PCIe, and I2C functional checks.

Partners transitioning from a 1RU NVL36 to 1RU NVL72 using the same compute tray, without any tray-level design changes, are allowed to leverage all their L10 validation.

For L11 rack-level validation, partners must complete the line items outlined in the PVP on their NVL72 rack system.

For additional test descriptions for the items listed in the following table, refer to the *GB200 NVL System Partner Validation Playbook* (NVOnline: 1115639) and the *GB300 NVL System Partner Validation Playbook* (NVOnline: 1128352).

Table 2-1. 2RU to 1RU Compute Tray Transition Test Items

ID	Category	Subcategory	Test Item
ME.9	Mechanical	Component fit check	Check all components fit inside tray
LC.5	Liquid Cooled	LC Tray Leak - Small Leak Detection	Trigger a small liquid leak (slow dripping) in a tray using PG25
LC.8	Liquid Cooled	LC Tray Leak - Disconnect Sensor Fault	Unplug the leak detection sensor from the board
TH.20	Thermal	Thermal Stress Test (NVQual Test #1)	Full power thermal stress test with all external components (that is, InfiniBand, SSD) at worst case ambient (chamber required)
PW.1	Power	Power EDPp (NVQual Test #7)	NVQual Test#7 - Input power EDP peak testing for system power supplies
EC.1	PCIe	PCIe EOM (NVQual Test #17)	Qualification - 50x PCIe EOM Margin Test with a PASSING EOM as per vendor spec
EC.2	PCIe	PCIe hot reset (NVQual Test #24)	LTSSM - 10000x Hot Reset - SBR with training

ID	Category	Subcategory	Test Item
EC.3 -12	PCIe	PCIe Speed Change LTSSM (NVQual Test #29)	LTSSM - 500x Speed Change
EC.13	PCIe	PCIe link enable disable (NVQual Test #26)	LTSSM - 10000x PCIe Link Enable/Disable
EC.14	PCIe	PCIe retrain (NVQual Test #27)	LTSSM - 10000x PCIe retrain
EC.15	PCIe	PCIe L1 transitions (NVQual Test #30)	LTSSM - 10000x Power management L1 transition
EC.16	PCIe	PCIe D3 transitions (NVQual Test #31)	LTSSM - 10000x Power management D3 transition
EC.17	PCIe	PCIe Tx Equalization Test (NVQual Test #25)	LTSSM - 10000x Tx Eq Redo
IC.5	I2C	BMC I2C-6, and UPHY1 1P functional	Test connections between BMC I2C-6 and UPHY1 from the first Bianca compute board
IC.6	I2C	BMC I2C-6 and UPHY1 2P functional	Test connections between BMC I2C-6 and UPHY1 from the second PG548
IC.7	I2C	BMC I2C-6, and UPHY0 1P functional	Test connections between BMC I2C-6 and UPHY0 from the first PG548
IC.8	I2C	BMC I2C-6 and UPHY0 2P functional	Test connections between BMC I2C-6 and UPHY0 from the second PG548
IC.9	I2C	BMC I2C-6, Mezzanine Network Board 1 IO expander, and FRU functional	Test connections between BMC I2C-6 and Mezzanine Network Board 1 I/O expander and FRU
IC.10	I2C	BMC I2C-6, Mezzanine Network Board 2 I/O expander, and FRU functional	Test connections between BMC I2C-6 and Mezzanine Network Board 2 I/O expander and FRU
IC.11	I2C	BMC I2C-1 SSIF functional	Test SSIF connection between FPGA and BMC I2C-1
IC.17	I2C	BMC I2C-3, HMC I2C-4 and FPGA 1 functional	Test connections between FPGA #1, FPGA #1 ERoT, HMC I2C-4, HMC FRU and BMC I2C-3
IC.19	I2C	BMC I2C-2, HMC I2C-1, HMC ERoT, and FPGA 2 functional	Test connections between BMC, HMC ERoT, HMC I2C-1, FPGA #2 ERoT and FPGA #2
IC.22	I2C	HMC I2C-13, BMC I2C-16 and UPHY3 2P functional	Test connections between HMC I2C-13, BMC I2C-16 and UPHY3 from second PG548
IC.23	I2C	BMC I2C-5, RTC and I/O expander functional	Test connections between BMC I2C-5, RTC and I/O expander
IC.24	I2C	BMC I2C-6 and I2C Switches functional	Test connections between BMC I2C-6 and I2C Switches on both carrier boards
IC.25	I2C	BMC I2C-7, PDB, Leak Sensors, and Fan controllers functional	Test connections between BMC I2C-7, both boards fan controllers, leak sensors, and PDB board
IC.26	I2C	BMC I2C-9, HMC-7, and M.2 functional	Test connections between BMC I2C-9, HMC-7 and M.2

ID	Category	Subcategory	Test Item
IC.27	I2C	BMC I2C-10 and I/O expanders functional	Test connections between BMC I2C-10 and I/O expander on HMC and both I/O expanders on both carrier boards
IC.28	I2C	BMC I2C-11, TMP, and BMC FRU functional	Test connections between BMC I2C-11, temperature sensor, and BMC FRU
IC.29	I2C	BMC I2C-15 and UPHY3 1P functional	Test connections between BMC I2C-15 and UPHY3 from the first PG548
SY.5	System	Warm reboot test	Test that the system can perform a warm reboot
SY.6	System	AC reboot test	Test that the system can AC cycle (aux cycle)
SY.7	System	DC reboot test	Test that the system can DC cycle (run power from BMC)
SY.8	System	DC 2 reboot test	Test that the system can DC cycle (run power and standby power from BMC)
SY.15	System	AC reboot stress test	100x AC cycles by completely removing power from tray, checking for reliable power control and ensuring OS, PCIe, MCTP, SSIF, and FPGA stability each cycle
SY.16	System	DC reboot stress test	100x DC cycles (run power and standby power from BMC), check for reliable power control, and ensure OS, PCIe, MCTP, SSIF and FPGA stability each cycle
SY.25	System	System Inventory check	Check the inventory (FRU list) of every node in the chassis
SY.33	System	Tray hot swap	Unplug a tray while the system is turned on and plug it back in

Chapter 3. L10 Compute Tray Hardware Validation

This chapter describes additional recommended hardware validation items of the L10 compute tray.

3.1 Mechanical

Partners should go through the following items in Table 3-1 to verify the mechanical integration of the compute tray.

Table 3-1. Mechanical Checklist

ID	Subcategory	Test Item Description	Expected Results
ME.1	Mechanical fitment of all PCBAs	Check the mechanical fit of all the PCBAs	All PCBAs fit in the expected location and screw holes align with the chassis
ME.2	Mechanical Tray Weight	Physically weigh the tray	Weight is in line with target weight
ME.3	Physical Interference	Inspect the tray for interferences or overstressed components under normal use cases	No component is overstressed and there are no mechanical interferences
ME.4	Cable Routing Path	Check all cable routing paths within the tray	Ensure all cables are routed along the correct path
ME.5	Cable Routing Slack	Check all cable lengths during normal operation in the tray	Ensure all cables are the correct length with no excessive slack or cables under stress
ME.6	Cable Routing Radii	Check all cable bend angles and locations in the tray	Ensure all cable bends are not exerting excessive stress on the cable
ME.7	Cable Labeling	Check all cable labeling on all cables within the tray	Ensure all cables are correctly labeled within the tray
ME.8	Tray Labeling	Check all tray labeling within the tray and on the outside of the tray	Ensure all labeling on and in the tray are correct

ID	Subcategory	Test Item Description	Expected Results
ME.9	Component fit check	Check all components fit inside tray	All components fit as expected and can be successfully installed into the tray
ME.10	Tray screw alignment	Check all board screw holes align with tray screw holes	All boards and component screw holes align with tray screw holes
ME.11	Liquid pipe routing path	Check all liquid pipe routing paths within the tray	Ensure all liquid pipes are routed along the correct path
ME.12	Liquid pipe routing slack	Check all liquid pipe lengths during normal operation in the tray	Ensure all liquid pipes are correct length with no excessive slack or cables under stress
ME.13	Liquid pipe routing radii	Check all liquid pipe bend angles and locations in the tray	Ensure all liquid pipe bends are not exerting excessive stress on the cable

3.2 Thermal

This section details the thermal testing and procedures for the GB200 and GB300 NVL systems.

3.2.1 Host BMC Shdn, Event Logging for THERM_OVERT_N Assertion

Purpose

The purpose of this test is to ensure that the partner takes the correct action within their BMC if components within the baseboard rise above the maximum operating temperature.

Prerequisites

- > Download the error injection toolkit within the *NVIDIA RASTool (NVRASTool)* (NVOnline:1112947) and follow instructions within the user's guide for any prerequisites required to run the toolkit on your host machine.
- > Implement a logging mechanism within the host BMC to log events, such as overtemperature, in non-volatile storage for RMA and debug analysis.

Test Procedure

1. Within the NVRASTool, assert hardware injection fault conditions to emulate a **THERM_OVERT_N**. By injecting an overtemperature condition within the following baseboard components, we can assert the **THERM_OVERT_N** signal:
2. Ensure that **THERM_OVERT_N** is asserted through the Out-of-Band (OOB) path.
3. Upon triggering **THERM_OVERT_N**, ensure the host system shuts down the baseboard within 1 second by de-asserting **GPU_BASE_PWR_EN** or **GPU_BASE_STBY_EN**.
4. Log the overtemperature event in the BMC.

5. Power cycle the system chassis to reset the fault.

Pass or Fail Criteria

- > The baseboard remains in a shutdown state until human intervention
- > The BMC logs the **THERM_OVERT_N** event in non-volatile storage for RMA and debug analysis

3.2.2 Host BMC Shdn, Event Logging for FPGA_OVERT_N Assertion

Purpose

The purpose of this test is to ensure that the partner takes the correct action within their BMC if the FPGA rises above the maximum operating temperature.

Prerequisites

- > Download the error injection toolkit within the *NVIDIA RASTool (NVRASTool)* (NVOnline: 1112947) and follow instructions within the user's guide for any prerequisites required to run the toolkit on your host machine.
- > Implement a logging mechanism within the host BMC to log events, such as overtemperature, in non-volatile storage for RMA and debug analysis.

Test Procedure

1. Within the NVRASTool, assert hardware injection fault conditions to emulate an **FPGA_OVERT_N**.
2. Ensure that **FPGA_OVERT_N** is asserted through the Out-of-Band (OOB) path.
3. Upon triggering **FPGA_OVERT_N**, ensure the host system shuts down the baseboard within 1 second by de-asserting **GPU_BASE_PWR_EN** or **GPU_BASE_STBY_EN**.
4. Log the FPGA overtemperature event in the BMC.
5. Power cycle the system chassis to reset the fault.

Pass or Fail Criteria

- > Ensure the baseboard remains in a shutdown state until human intervention
- > Ensure that the BMC logs the **FPGA_OVERT_N** event in non-volatile storage for RMA and debug analysis.

3.3 Liquid Cooling

This section details the liquid cooling testing and procedures for the GB200 and GB300 NVL systems.

3.3.1 Leak Detection

Purpose

Verify that the leak detection features on the compute tray are detecting liquid properly. Partners can verify the hardware feature through ADC readouts before checking the BMC firmware implementation. Refer to the *NVIDIA MGX Leak Detection Strategy and Remediation Application Note* (NVOnline: 1115991) for more information.

Prerequisites

Leak sensors are connected to the compute board. They do not need to be fully integrated into the tray chassis.

Test Procedure

1. Test the leak sensor ADC readings under dry, nominal conditions. Verify that the ADC normalized readings are within the defined passing threshold (0.49 – 0.55).

2. Stop the BMC Leak Detector service, the example code is as follows. Partners will need to modify the following command per their BMC implementation.

```
systemctl stop xyz.openbmc_project.leakdetectsensor.service #This application should
automatically restart on next BMC reset
```

3. Unbind the drivers dependent on what ADCs you have connected.

```
echo ${ADC_ADDR} > /sys/bus/i2c/devices/i2c-6/delete_device #ADC_ADDR = [0x34, 0x35,
0x18, 0x1E]
```

4. For example, if you have a system with MAX1363 ADC parts:

```
root@gb200nvl-bmc:/# i2cdetect -y -q 6
    0  1  2  3  4  5  6  7  8  9  a  b  c  d  e  f
00:                ---- 0c  --  --  --
10: --  -- 12  -- 14  --  --  --  --  --  --  --  --  --
20: UU  --  -- UU  --  --  -- 28  --  --  -- UU  --  -- UU
30: --  --  --  -- UU UU  -- 37  --  --  --  --  --  --
40: --  --  --  --  --  --  --  --  --  --  -- 4e  --
50: UU  --  --  --  --  --  --  --  --  --  --  --  --
60: 60 61  --  --  --  --  --  --  --  --  --  --  --
70: --  --  --  --  --  --  --  --  --  --  --  --

root@gb200nvl-bmc:/# systemctl stop xyz.openbmc_project.leakdetectsensor.service
root@gb200nvl-bmc:/# echo 0x34 > /sys/bus/i2c/devices/i2c-6/delete_device
root@gb200nvl-bmc:/# echo 0x35 > /sys/bus/i2c/devices/i2c-6/delete_device
root@gb200nvl-bmc:/# i2cdetect -y -q 6
    0  1  2  3  4  5  6  7  8  9  a  b  c  d  e  f
00:                --  --  --  -- 0c  --  --  --
10: --  -- 12  -- 14  --  --  --  --  --  --  --  --  --
20: UU  --  -- UU  --  --  -- 28  --  --  -- UU  --  -- UU
30: --  --  --  -- 34 35  -- 37  --  --  --  --  --  --
40: --  --  --  --  --  --  --  --  --  --  -- 4e  --
50: UU  --  --  --  --  --  --  --  --  --  --  --  --
60: 60 61  --  --  --  --  --  --  --  --  --  --  --
70: --  --  --  --  --  --  --  --  --  --  --  --
```

- Restart the BMC Leak Detector service and re-bind the ADCs.

```
systemctl start xyz.openbmc_project.leakdetectsensor.service
```

- Getting the ADC readings before applying liquid to the leak detection sensor. Each ADC has two channels.

```
# Primary Bianca AIN0
```

```
root@gb200nvl-bmc:/# i2cttransfer -y -f 6 w2@0x34 0x61 0x82 r2
0x98 0x54
```

```
# Primary Bianca AIN1
```

```
root@gb200nvl-bmc:/# i2cttransfer -y -f 6 w2@0x34 0x63 0x82 r2
0xb8 0x4b
```

```
# Secondary Bianca AIN0
```

```
root@gb200nvl-bmc:/# i2cttransfer -y -f 6 w2@0x35 0x61 0x82 r2
0x98 0x58
```

```
# Secondary Bianca AIN1
```

```
root@gb200nvl-bmc:/# i2cttransfer -y -f 6 w2@0x35 0x63 0x82 r2
0xb8 0x4a
```

- Convert the ADC readings to the voltage value and compare the read-out value from the ADC sensors to the nominal threshold range. Take the lower 12 bits of the reading you got from the previous step and convert it to a decimal value. Then divide it by 4095 and multiply by 3.3 to get the ADC voltage reading.

```
# Primary Bianca AIN0
```

```
root@gb200nvl-bmc:/# i2cttransfer -y -f 6 w2@0x34 0x61 0x82 r2
0x98 0x54
```

- To convert the sensor reading "0x98 0x54" we take the lower 12 bits so that is 0x854 which is equal to 2132. Now divide this by 4095 and multiply by 3.3. $(2132/4095)*3.3 = 1.718V$

For normalized readings, just divide by 4095 so $2132/4095 = 0.52$

- Repeat the same exercise after applying liquid droplets to the leak sensors at the GPU sensor (P4672) and the manifold sensor (P4674). Partners can choose to apply additional leak testing at other sensor locations as well.



Note: Care should be taken when applying liquid droplets on the liquid sensors. Partners are recommended to have the leak sensor outside the tray assembly. Apply droplets to the sensor directly to avoid damaging other electronic components.

- Repeat the same exercise after shorting the sensor through a jump wire and verify that the nominal ADC reading is at or close to zero.
- Repeat the same exercise when the sensor is unplugged from the compute tray (missing sensor condition). Verify that the nominal ADC reading is at or close to one.

Pass or Fail Criteria

- > Sensor ADC hardware pass or fail criteria:
 - For a dry, no leakage condition, the normalized ADC reading should be between 0.49 and 0.55.
 - For a leakage condition, the resistance across the sensor will drop resulting in a lower voltage input to the ADC. As a result, the normalized ADC reading should be lower than 0.49.
 - For a sensor short condition, the normalized ADC reading should be at or close to zero.
 - For a missing sensor condition, the normalized ADC reading should be at or close to one.
- > BMC firmware implementation pass or fail criteria:
 - For any fault condition (leakage, short, missing sensor), the amber fault LED on the front panel should be blinking at 4 Hz.
 - The BMC should support DMTF Redfish LeakDetection and LeakDetector schemas. Verify the Redfish event log should be issued by the BMC. The fault event log should be located in the Redfish event log directory, for example:
`/redfish/v1/Systems/System_0/LogServices/EventLog`

3.4 Power Validation

This section details the power validation testing and procedures for the GB200 and GB300 NVL systems.

3.4.1 Input EDP Peak Testing

Purpose

This test validates that the system can operate under transient workload at various pulsing frequencies and that the input voltage peak-to-peak value is within the values listed in the product specification.

For board level input EDPp specifications, refer to the *NVIDIA GB200 NVL Bianca Compute Board Product Specification* (NVOnline: 1114953) and the *NVIDIA GB300 NVL 72 HPM Compute Board Product Specification* (NVOnline: 1126424).

Test Procedure

1. Secure probe point for the input power on the 12V bus bar going into the compute board PCBA.
2. Run the NVQual Test #7 (Input EDPp Test)
3. On the 12V voltage rail, capture the instantaneous voltage peak-to-peak value, and compare it against the product specification for peak-to-peak value.
4. To accurately characterize input EDPp transient current and power, there are two measurement methods:

- a. Use the oscilloscope's "**High Res**" feature in the oscilloscope that oversamples and then averages over the acquisition interval. For the board level and compute tray level specifications, the moving average timescales are 400 μ s and 50 ms. See **Section 6.1 "Moving Average Measurement using Oscilloscope HiRes Mode"** for more information.
- b. Collect data samples over the transient workload and perform post processing for each load frequency with the recommended oscilloscope settings. See **Section 6.2 "Input EDPp Post-Processing Guideline"** for more information.
 - i. Sampling rate:
 - (1) Load frequencies < 10 KHz: 100 μ s/pt is sufficient
 - (2) Load frequencies \geq 10 KHz: 40 μ s/pt is recommended
 - ii. Record length and horizontal scale:
 - (1) Load frequencies < 10 KHz: 1500 seconds (150 sec/div)
 - (2) Load frequencies \geq 10 KHz: 1200 seconds

Pass or Fail Criteria

Ensure that the compute tray does not crash when running the workload and that the peak-to-peak voltage noise is within the product's electrical specification.

3.4.2 GPU Power Brake

Purpose

This test ensures that the partner has the capability to assert the power brake (**PWR_BRAKE_N**) to lessen peak and continuous power draw during emergency situations.

Test Procedure

1. Ensure that the **PWR_BRAKE_N** signal is in a de-asserted state before the experiment during normal operation.
2. If power brake is implemented for the emergency scenarios, toggle the **PWR_BRAKE_N** external input.
 - a. Assert **PWR_BRAKE_N** for at least 250 ms on the host partner system.
3. Verify total baseboard power gets reduced when **PWR_BRAKE_N** is asserted.
 - a. Run tools such as NVQual thermal test or nvidia-smi for log collection on GPU power levels and GPU clock.

Pass or Fail Criteria

- > **PWR_BRAKE_N** is in a de-asserted state during normal operation.
- > **PWR_BRAKE_N** is asserted by the host platform for all emergency scenarios.

3.4.3 Power Distribution Board Static Loads

Purpose

The purpose of this test is to verify that the partner-designed power distribution board (PDB) can supply and sustain power under various static load conditions. For more information, refer to the *GB200 NVL72 Compute Tray Power Distribution Board Design Specification* (NVOnline: 1115461) and the *NVIDIA GB300 NVL72 Power Distribution Board Design Specification* (NVOnline: 1136956).

Prerequisites

PDB board with an electronic load to simulate active load.

Some of the GB NVL72 compute tray components are partner designed, and partners are responsible for validating to the power budget of their compute tray. The following test condition and procedure are for partner reference only.

Test Procedure

1. Connect electronic load to all power rails **12V_RUN_1**, **12V_RUN_2**, and **12V_STBY** on the PDB board with the 54V input power to the PDB.
2. Start from 0% static load and draw power from the PDB.
3. Sweep static load conditions with increasing steps (partner defined, a minimum of 4 to 5 steps), until PDB power protection hot swap controller (HSC) over current protection kicks in.
4. Record input voltage, output voltage, and current for each step.

Pass or Fail Criteria

- > PDB can sustain all static load conditions before OCP without any issues.
- > The PDB board did not sustain any permanent damage after OCP.

3.4.4 Power Distribution Board Dynamic Loads

Purpose

This test's purpose is to verify that the partner-designed power distribution board (PDB) can supply and sustain power under various dynamic load conditions. For more information, refer to the *GB200 NVL72 Compute Tray Power Distribution Board Design Specification* (NVOnline: 1115461) and the *GB300 NVL72 Power Distribution Board Design Specification* (NVOnline: 1136956).

Prerequisites

PDB board with an electronic load to simulate active load.

Some of the GB NVL72 compute tray components are partner designed, partners are responsible for validating to the power budget of their compute tray. The following test condition and procedure are for partner reference only.

Test Procedure

1. Connect electronic load to all power rails **12V_RUN_1**, **12V_RUN_2**, and **12V_STBY** on the PDB board with the 54V input power to the PDB.
2. For the electrical load setting, with 50% duty cycle at 10 ms, 20 ms, and 50 ms at 100% load.
3. Test at 10% duty cycle at maximum load at the board hot swap controller (HSC) over current protection kicks in.
4. Record input voltage, output, voltage and current for each step.

Pass or Fail Criteria

- > PDB can sustain all load conditions before OCP without any issues.
- > The PDB board did not sustain any permanent damage after OCP.

3.5 PCIe

This section details the PCIe testing and procedures for the GB200 and GB300 NVL systems.

3.5.1 PCIe Speed and Width Configuration Check

Purpose

This test is to verify that all NVIDIA Grace™ PCIe lanes are configured to their expected speed and width.

Prerequisites

The following table shows the minimum required hardware configuration for verifying the CPU UPHY PCIe width and speed. Partners can prioritize validating PCIe links that do not require GPUs to ensure faster time to market.

Table 3-2. PCIe Link Specification and Minimum Hardware Configuration

#	PCIe Link	Width	Speed	Minimum Hardware Configuration
1	Grace 0 UPHY 0 (#1 CX-7/CX-8) (x16)	x16	Gen5	Full Tray + GPU-Less
2	Grace 0 UPHY 1 (#2 CX-7/CX-8) (x16)	x16	Gen5	Full Tray + GPU-Less
3	Grace 0 UPHY 2 (PEX SW Gen 3) (x1)	x1	Gen3	Full Tray + GPU-Less
4	Grace 0 UPHY 2 (1G NIC) (x1)	x1	Gen3	Full Tray + GPU-Less
5	Grace 0 UPHY 2 (USB Bridge) (x1)	x1	Gen2	Full Tray + GPU-Less
6	Grace 0 UPHY 2 (DC-SCI) (x1)	x1	Gen2	Full Tray + GPU-Less
7	Grace 0 UPHY 3 (BF-3) (x16)	x16	Gen5	Full Tray + GPU-Less
8	Grace 0 UPHY 3 (4 x E1.S) (x4)	x4	Gen4	Full Tray + GPU-Less
9	Grace 0 UPHY 4 (GPU/CX-8) (x1)	x1	Gen4	Core Tray

#	PCIe Link	Width	Speed	Minimum Hardware Configuration
10	Grace 0 UPHY 5 (GPU/CX-8) (x1)	x1	Gen4	Core Tray
11	Grace 1 UPHY 0 (#1 CX-7/CX-8) (x16)	x16	Gen5	Full Tray + GPU-Less
12	Grace 1 UPHY 1 (#2 CX-7/CX-8) (x16)	x16	Gen5	Full Tray + GPU-Less
13	Grace 1 UPHY 2 (M.2 SSD) (x4)	x4	Gen4	Full Tray + GPU-Less
14	Grace 1 UPHY 3 (BF-3) (x16)	x16	Gen5	Full Tray + GPU-Less
15	Grace 1 UPHY 3 (4 x E1.S) (x4)	x4	Gen4	Full Tray + GPU-Less
16	Grace 1 UPHY 4 (GPU/CX-8) (x1)	x1	Gen4	Core Tray
17	Grace 1 UPHY 5 (GPU/CX-8) (x1)	x1	Gen4	Core Tray

Test Procedure

Run the following from the host and check the speed and width of each device in the output:

```
sudo lspci -vvv
```

Pass or Fail Criteria

Verify each link conforms to the speed and width listed in Table 3-2.

3.5.2 PCIe Link Training Steady State Machine

PCIe Link Training Steady State Machine (LTSSM) should be carried out on all the PCIe links from the Grace CPU. Partners may be able to perform certain links before a fully populated Bianca board with GPUs. The PCIe LTSSM includes the following tests and should be performed on all Grace PCIe links.

Table 3-3. Grace CPU PCIe LTSSM

Test	Subtest	Iterations	Pass or Fail Criteria
Link Inoperability	Hot Reset - SBR	10000	Train to device maximum Speed and Width with no Uncorrectable or Correctable Errors logged.
	Speed Change (Gen1 - Gen2)	500	Train to Gen2 x16 No errors
	Speed Change (Gen1 - Gen3)	500	Train to Gen3 x16 No errors
	Speed Change (Gen1 - Gen4)	500	Train to Gen4 x16 No errors
	Speed Change (Gen1 - Gen5)	500	Train to Gen5 x16 No errors
	Speed Change (Gen2 - Gen3)	500	Train to Gen3 x16 No errors
	Speed Change (Gen2 - Gen4)	500	Train to Gen4 x16 No errors
	Speed Change (Gen2 - Gen5)	500	Train to Gen5 x16 No errors
	Speed Change (Gen3 - Gen4)	500	Train to Gen4 x16 No errors
	Speed Change (Gen3 - Gen5)	500	Train to Gen5 x16 No errors

Test	Subtest	Iterations	Pass or Fail Criteria
	Speed Change (Gen4 - Gen5)	500	Train to Gen5 x16 No errors
	Link Disable/Enable	10000	Train to device maximum Speed and Width with no Uncorrectable or Correctable Errors logged.
	Retrain	10000	Train to device maximum Speed and Width with no Uncorrectable or Correctable Errors logged.
	PowerManagement L1 Transitions	10000	Train to device maximum Speed and Width with no Uncorrectable or Correctable Errors logged.
	PowerManagement D3 Transitions	10000	Train to device maximum Speed and Width with no Uncorrectable or Correctable Errors logged.
	Tx Eq Redo	10000	Train to device maximum Speed and Width with no Uncorrectable or Correctable Errors logged.

Prerequisites

Partners must use NVQual vG1.0.4 or later

Test Procedure

1. Download the *NVQual for Grace-Blackwell Product* (NVOnline: 1119931) and follow the instructions within the *NVQual User's Guide*.
2. Select and run the PCIe Link Training test suite under NVQual.
3. Verify the NVQual output test result and check against the minimum hardware configuration in Table 3-2 to make sure they can successfully run the PCIe LTSSM
4. Update the test results on the Partner Validation Playbook.
5. Combine these test logs into a single ZIP file for the final NVQual submission
6. Refer to the *Introduction to NVIDIA Partner Validation Playbook (PVP)* (NVOnline: 1106745) for instructions on test results submission.

Pass or Fail Criteria

PCIe LTSSM test passes in the NVQual test tool.

3.6 I/O Interface

This section details the I/O interface testing and procedures for the GB200 and GB300 NVL systems.

3.6.1 CPU JTAG Scan Check from BMC

Purpose

This test checks the debug JTAG scan from a single Grace CPU to the BMC is functional as expected.

Prerequisites

Partner should use minimum QS firmware package dev1 drop, and with C05 Bianca board.

Test Procedure

1. Set the **JTAG_MUX_SEL** to active low on the BMC

```
root@gb200nvl-bmc:~# gpioset `gpiofind "JTAG_MUX_SELECT-0"`=1
```
2. Set the **JTAG_BYPASS_B2B** to 1 from the HMC via SMBPBI

```
i2cset -y 1 0x60 0x5c 0x04 0xb4 0x99 0x56 0x80 i # unlock hidden devices via SMBPBI
```
3. Set the I/O expander (4th bit) to 1 from the HMC

```
root@gb200nvl-hmc:~# i2ctransfer -y 1 w3@0x0f 0x38 0x02 0x08
```
4. Using the `jtag_test` code attached in this validation guide, and run the test code

```
root@gb200nvl-bmc:~# ./jtag_test -j /dev/jtag1 -i 0x6ba00477 -f 1000000 -v
```
5. Verify the number of devices found, expected to be 1: Verify the ID code of the found device, expected to be 0x6ba00477

```
Found number of devices:1
Found ir length devices:4
idcode:0x6ba00477
```



Note: To access the attached test code "jtag_test," click the **Attachment** icon on the left-hand toolbar on this PDF (using Adobe Acrobat Reader or Adobe Acrobat). Select the file and use the Tool Bar options (**Open**, **Save**) to retrieve the attachment. File with the .nvzip extension must be renamed to .zip and then can be extracted using 7-zip file archive software or other archive software.

Pass or Fail Criteria

CPU JTAG can successfully complete the boundary scan from the BMC. The number of devices and device ID code matches the expected values.

3.6.2 Dual CPU JTAG Scan Check from BMC

Purpose

This test checks the debug JTAG scan from two Grace CPUs to the BMC is functional as expected.

Prerequisites

Partner should use minimum QS firmware package dev1 drop, and with C05 Bianca board.

Test Procedure

1. Set the **JTAG_MUX_SEL** to active low on the BMC

```
root@gb200nvl-bmc:~# gpioset `gpiofind "JTAG_MUX_SELECT-0"`=1
```
2. Set the **JTAG_BYPASS_B2B** to 1 from the HMC

```
i2cset -y 1 0x60 0x5c 0x04 0xb4 0x99 0x56 0x80 i # unlock hidden devices via SMBPBI on Primary Board
i2cset -y 2 0x60 0x5c 0x04 0xb4 0x99 0x56 0x80 i # unlock hidden devices via SMBPBI on Secondary Board
```
3. Set the I/O expander (4th bit) to 1 on the secondary board

```
root@gb200nvl-hmc:~# i2ctransfer -y 2 w3@0x0f 0x38 0x02 0x08
```
4. Using the `jtag_test` code attached in this validation guide, and run the test code

```
root@gb200nvl-bmc:~# ./jtag_test -j /dev/jtag1 -i 0x6ba00477 -f 1000000 -v
```
5. Verify the number of devices found, expected to be 2. Verify the ID code of the found device, expected to be 0x6ba00477)

```
Found number of devices:2
Found ir length devices:8
idcode:0x6ba00477
idcode:0x6ba00477
```



Note: To access the attached test code “jtag_test,” click the **Attachment** icon on the left-hand toolbar on this PDF (using Adobe Acrobat Reader or Adobe Acrobat). Select the file and use the Tool Bar options (**Open, Save**) to retrieve the attachment. File with the .nvzip extension must be renamed to .zip and then can be extracted using 7-zip file archive software or other archive software.

Pass or Fail Criteria

CPU JTAG can successfully complete the boundary scan from the BMC. The number of devices and device ID code matches the expected values.

3.6.3 CPU JTAG Electrical Validation

Purpose

This test checks the debug JTAG electrical signal meets the JTAG timing requirements as referenced in the Arm developer RealView ICE.

Figure 3-1. CPU JTAG Electrical Validation




Table 3-4. JTAG Timing Specification

Symbol	Parameter	Min.	Max.
Tbscl	TCK LOW period	50 ns	500 μ s
Tbsch	TCK HIGH period	50 ns	500 μ s
Tbsod	TDI and TMS valid from TCK falling edge	--	6.0 ns
Tbsis	TDO setup to TCK (rising)	15.0 ns	--
Tbsih	TDO hold from TCK (rising)	6.0 ns	--

Prerequisites

Partner should use minimum QS firmware package dev1 drop, and with C05 Bianca board.

Test Procedure

1. Set the CPU ready for JTAG scan chain as in Section 3.6.1.
2. Install probe points at the BMC board for JTAG signals (TDI, TDO, TCK, and TMS)
3. Capture waveforms when the jtag_test code is executed.

Pass or Fail Criteria

Verify that the captured JTAG signals meet the timing specification listed in Table 3-4.

3.6.4 I2C Functional Bus Scan

Purpose

This test ensures that the host BMC can access all other I2C buses in the compute tray as outlined in the *NVIDIA GB200 Bianca NVL Product Specification* (NVOnline: 1114953).

Prerequisites

- > Set up the partner's Host BMC or equivalent I2C host device with access to the I2C buses.
- > Identify which I2C addresses need to be accessed within the host I2C device.
- > Ensure that your I2C host device has the correct parameters set:
 - Bitrate
 - Slave address
 - Disable internal I2C pull-up resistors within the host I2C device

Test Procedure

Perform a read on the host I2C device with connections to SDA and SCL lines. For example, systems with Linux packages such as I2C tools installed on the BMC or HMC can utilize the following commands for scanning:

```
I2C1 scan: i2cdetect -y -q $I2C1_BUS
I2C2 scan: i2cdetect -y -q $I2C2_BUS
```

Pass or Fail Criteria

All device I2C addresses are visible through the I2C bus scan.

3.6.5 I2C Electrical Validation

Purpose

This test ensures the I2C management interface meets the official I2C electrical specifications (<https://www.nxp.com/docs/en/user-guide/UM10204.pdf>).

Prerequisites

- > Set up oscilloscope with passive probes (1 MHz bandwidth per channel or higher)
- > Ensure direct probing access to I2C buses highlighted in the *NVIDIA GB200 NVL Bianca Compute Board Product Specification* (NVOnline: 1114953). This may require soldering break-out wires to the net name locations outside of the baseboard.
- > Set up host BMC or equivalent I2C host device
 - Establish a method of sending I2C traffic to the host BMC. For example, set up polling to the I2C bus or develop a script to read data from an I2C endpoint through OOB methods.
- > Ensure that your I2C host device has the correct parameters set:
 - Bitrate
 - Slave address
 - Register address
 - Disable internal I2C pull-up resistors within the host I2C device

Test Procedure

1. Hook up the oscilloscope and passive probes (2x) to the SDA and SCL lines on the I2C bus.

2. Initiate I2C read/write traffic with host I2C device.
3. Collect I2C waveforms for each I2C electrical validation parameter.

Pass or Fail Criteria

The measurements performed on the I2C buses must meet the official electrical specifications by Philips/NXP. I2C parameters should be verified:

- > V_OL (Output Low Voltage)
- > V_OH (Output High Voltage)
- > Clock Frequency
- > Rise Time
- > Fall Time
- > High Time
- > Low Time
- > Setup Time
- > Hold Time
- > Hold Time – Start
- > Setup Time – Stop

3.6.6 SPI Functional Check

Purpose

Verify that SPI devices can be accessed and communicated properly.

Test Procedure

1. The example test procedure checks for BMC connection to the BMC ERoT (EID: 0) through MCTP on the SPI bus.
2. Use the following command to check for BMC ERoT is listed on the MCTP tree

```
root@dev:~# busctl tree xyz.openbmc_project.MCTP.Control.SPI
`- /xyz
   `-/xyz/openbmc_project
      `-/xyz/openbmc_project/mctp
         `-/xyz/openbmc_project/mctp/0
            `-/xyz/openbmc_project/mctp/0/0
```

3. SPI functionalities can be verified through the successful retrieval of the MCTP information (EIDs) on these ERoTs.
4. Use the following command to check for BMC to HMC ERoT by performing a HMC recovery from the BMC by SPI.

```
## From BMC Terminal ##
systemctl start hmc-recovery.target

busctl list | grep -i mctp    ## Verify SPI2 is available

busctl list | grep -i mctp
```



```

:1.179                                     2347 mctp-ctrl      root
:1.179      mctp-spi0-ctrl.service         -
-
:1.182                                     2403 mctp-ctrl      root
:1.182      mctp-i2c2-ctrl.service         -
-
:1.358                                     9600 mctp-ctrl      root
:1.358      mctp-i2c14-ctrl.service        -
-
:1.359                                     9601 mctp-ctrl      root
:1.359      mctp-i2c15-ctrl.service        -
-
:1.360                                     9602 mctp-ctrl      root
:1.360      mctp-i2c5-ctrl.service         -
-
:1.502                                     10310 mctp-ctrl     root
:1.502      mctp-spi2-ctrl.service         -
-
xyz.openbmc_project.MCTP.Control.SMBus14  9600 mctp-ctrl      root
:1.358      mctp-i2c14-ctrl.service        -
-
xyz.openbmc_project.MCTP.Control.SMBus15  9601 mctp-ctrl      root
:1.359      mctp-i2c15-ctrl.service        -
-
xyz.openbmc_project.MCTP.Control.SMBus2   2403 mctp-ctrl      root
:1.182      mctp-i2c2-ctrl.service         -
-
xyz.openbmc_project.MCTP.Control.SMBus5   9602 mctp-ctrl      root
:1.360      mctp-i2c5-ctrl.service         -
-
xyz.openbmc_project.MCTP.Control.SPI0     2347 mctp-ctrl      root
:1.179      mctp-spi0-ctrl.service         -
-
xyz.openbmc_project.MCTP.Control.SPI2     10310 mctp-ctrl     root
:1.502      mctp-spi2-ctrl.service         -
-
busctl tree xyz.openbmc_project.MCTP.Control.SPI2  ## Verify EID 1 Exists in the SPI2 Tree
`- /xyz
   `-- /xyz/openbmc_project
        `-- /xyz/openbmc_project/mctp
              |-- /xyz/openbmc_project/mctp/0
              | `-- /xyz/openbmc_project/mctp/0/1
              `-- /xyz/openbmc_project/mctp/SPI

```

Pass or Fail Criteria

Expected device EIDs show up on the MCTP SPI tree confirming the functionality of the SPI buses.

3.6.7 SPI Electrical Validation

Purpose

Verify that the SPI lines (MISO, MOSI, SCLK, SS/CS) on the partner BMC boards meet the SPI electrical specifications in terms of voltage levels, timing, and signal integrity. The SPI electrical signal should be verified against its timing specification outlined in Table 3-5.

Figure 3-2. SPI Electrical Validation




Table 3-5. SPI Timing Parameters


Symbol	Parameter	Unit	Min.	Max.
t_{CKH}	SCLK High Time	ns	8.6ns	$t_{CK} - t_{CKL}$
t_{CKL}	SCLK Low Time	ns	8.6ns	$t_{CK} - t_{CKH}$
t_{DO}	Data Output Propagation	ns	t_{DOH}	13ns
t_{DOH}	Data Output Hold time	ns	2	
t_{DIS}	Data Input Setup Time	ns	7.6	3000
t_{DIH}	Data Input Hold Time	ns	4	--
t_{CSS}	CS Input Setup Time	ns	19.6	--
t_{CSHR}	CS Input Hold Time	ns	9.8	--

Prerequisites

Equipment: Oscilloscope, signal generator, logic analyzer, and appropriate probes.

Test Procedure

- For the compute tray, the SPI voltage levels (V_{IH} , V_{IL} , V_{OH} , and V_{OL}) are configured to VDD at 3.3V. Refer to the device-specific data sheet for the DC electrical characteristics.
- Connect the oscilloscope probes to the SPI lines (DIN, DOUT, SCLK, SS/CS).
 - For checking the BMC to ERoT SPI path on the reference design, utilize the QSPI0 lines from the BMC to ERoT Microchip CEC1736.
 - For checking the BMC to HMC ERoT SPI path on the reference design, utilize the J21 connector on the HMC and measure the following bus nets:
EROT_OOB_BMC_CLK_MC, **EROT_OOB_BMC_CS0_MC**, **EROT_OOB_BMC_MOSI_MC**,
 and **EROT_OOB_BMC_MISO_MC**.



- Monitor the voltage levels for logic high and logic low on each line.
- Compare with the required voltage levels as per SPI specifications.
- Capture the timing of the SPI signals using the oscilloscope.
- Measure setup time, hold time, clock frequency, and clock-to-output delay.
- Verify that the timing parameters meet the SPI specification.
- Observe the SPI signals for any anomalies like noise, overshoot, or ringing.

Pass or Fail Criteria


- Signals must be clean without significant distortions or deviations from the expected waveform.
- Voltage levels must fall within the specified range for both logic high and low.
- Timing parameters must align with the SPI standard's specifications.

3.6.8 SGPIO Electrical Validation

The SGPIO communication protocol allows the FPGA on the Bianca compute board to communicate seamlessly across its accessory boards (BMC, HCM, and IPEX). It is also being used to feed various serialized signals to the FPGA using a parallel-to-serial shift buffer topology. For more information on SGPIO implementation on the compute board, refer to the *NVIDIA GB200 NVL Bianca Compute Board Product Specification* (NVOnline: 1114953).


The SGPIO bus consists of four signal lines and is shared between two devices, usually called initiator and target. It is an open collector configuration and typically has 2.0 k Ω pull-up resistors.

Figure 3-3. SGPIO Bus Overview



The following figure shows the timing parameters for SGPIO interface between the FPGA and BMC management module.

Figure 3-4. SGPIO Timing Diagram



These are the signals that make up the SGPIO bus:

- > **SClock:** The SGPIO interface from the Bianca FPGA is running at 12.5 MHz.
- > **SLoad:** Indicates a new frame of data and is synchronous to the clock. A new SGPIO frame is indicated by SLoad being high at a rising edge of a clock after having been low for at least five clock cycles. The four falling clock edges after a start condition are used to carry a 4-bit value from initiator to target, or vice versa.
- > **SDataOut:** Used by initiator to send data to target. Consists of 4-bit data packets
- > **SDataIn:** Used by target to send data back to initiator. Consists of 4-bit data packets.


Table 3-6. SGPIO Timing Parameters

Symbol	Parameter	Minimum	Maximum	Unit
f_{ck}	Clock frequency	-	12.5	MHz
t_{ldv}	LD valid delay	-	5	ns
t_{ov}	DATA_OUT valid delay	-	5	ns

Symbol	Parameter	Minimum	Maximum	Unit
t _{IS}	Input setup time	10	-	ns
t _{IH}	Input hold time	1	-	ns
T _R	Input rise time	-	6	ns
T _F	Input fall time	-	6	ns

Test Procedure

- Find SGPIO signals on the compute tray (Bianca) schematic.




- Determine a probing spot for each signal. See the following examples on the reference design.
 - The first set of signals already gives good test points. Measure LD and CLK near the FPGA at R83 and R5896, respectively. Measure data in near parallel to serial topology, or in this case R5897 which is near U739.
 - For the second set of signals, it is recommended that CLK, LD, and DATAOUT be measured near the FPGA. The image in Step 1 shows appropriate probing spots for these. DATAIN is to be measured as close as possible to the HMC. In this case, the HMC is the initiator, and the FPGA is the target.
- Locate probing spots on the layout file. Rework to add probes to necessary spots or acquire probe holders for testing the signals.



Note: If probes are to be added, make sure they are as short as possible so as not to introduce stubs to the physical layer of the communication bus and ensure proper grounding.

- Set up an oscilloscope with the appropriate signals to measure the timing and electrical properties of the bus and make sure they are in specification. Using the CLK or LD line as the scope's trigger would be best.



- Generate traffic and record multiple screenshots and waveform files. Make sure to record all necessary measurements, such as clock frequency, clock high and low time, rise and fall times, data setup, and hold times.

Pass or Fail Criteria

Check the captured signals against the PHY layer and protocol layer characteristics and verify against the SGPIO timing parameter provided in this section.

3.6.9 UART Functional Check

Purpose

UART is crucial for debugging the compute tray. Engineers and developers can directly tap into a device with a UART controller using a host PC if UART is functionally working. Partners should validate that the UART interfaces are functional and meet electrical specifications.


Test Procedure

- Identify the UART interface on the BMC module. This UART interface connects directly to the Grace CPU for debugging purposes.

- Identify the UART signals (TX, RX and GND lines) on the BMC, and connect the UART interface to a lab PC using a USB to TTL UART cable (example: <https://www.adafruit.com/product/954>)



- Verify that serial communication can be established between the UART controller and the lab PC. Partner can use a serial console terminal (that is, PuTTY, TeraTerm, or MobaXTerm) on the lab PC to confirm.
- Set the baud rate to match the baud rate (that is, 921600 bps) of the UART controller to ensure functional data transmission.



Pass or Fail Criteria

Ensure the UART serial communication is established between the lab PC and the BMC.


3.6.10 UART Electrical Validation

Purpose

Verify the UART interface between the BMC and the HMC CPLD meets the electrical specifications of the device data sheet.

Table 3-7. UART DC Specifications

Parameter	Symbol	Min	Typ	Max	Unit
Input low voltage	V_{IL}	-0.3	-	0.8	V
Input high voltage	V_{IH}	2.0	-	3.6	V
Output low voltage @ I_{OL} (min)	V_{OL}	-	-	0.4	V
Output high voltage @ I_{OH} (min)	V_{OH}	2.4	-	-	V

Figure 3-5. UART T_{BIT} Definition**Table 3-8. UART AC Specifications**

Parameter	Symbol	Min	Typ	Max	Unit
Baud Rate	-	-	-	3.6864	MBits/s
Bit Time	T_{BIT}	271	-	-	ns
Input/Output Rise Time	T_R	-	-	0.05	T_{BIT}
Input/Output Fall Time	T_F	-	-	0.05	T_{BIT}



Note: The procedure outlines the UART parameters based on the reference BMC and HMC device AST2600. Refer to the specific SoC data sheet for the corresponding parameters.

Prerequisites

- > Oscilloscope: Tektronix TDS684C or faster
- > At least one (preferably four) Tektronix P6245 Single-ended Probes (with dynamic range of 7+ volts)
- > USB to TTL UART cable

Test Procedure

1. Identify the UART TX, RX pin location on the MICO connector between the HMC and BMC board
2. Send UART signals between via the BMC to the HMC CPLD, and capture waveforms on scope.
3. Check the captured waveform against the DC and AC electrical specifications with the respective device data sheet, or as outlined in Table 3-7 and Table 3-8.

Pass or Fail Criteria

Ensure the UART waveform captured meets both the DC and AC electrical specifications as outlined.

3.6.11 RMII Network Controller Sideband Interface

NC-SI, abbreviated from network controller Sideband interface, is an electrical interface and protocol defined by the Distributed Management Task Force (DMTF). The NC-SI enables the connection of a baseboard management controller (BMC) to one or more network interface controllers (NICs) in a server computer system to enable out-of-band system management. This allows the BMC to use the network connections of the NIC ports for the management traffic, in addition to the regular host traffic.

NC-SI is based on the RMII specification with some modifications that allow the connection of multiple network controllers to a single BMC.

The NC-SI port allows OOB management to the BMC and BF-3 from the BF-3's QSFP network. It may be seen that this link allows the BMC to talk directly to the BF-3 over IP, but this is not the case. The BMC's eth1 link is forwarded directly to the external QSFP network.


Purpose

Verify the RMII NC-SI communication between the BMC and BF-3 is functional without any package lost.

Prerequisites

Minimum hardware requirements:

- > 1x compute board (Bianaca or Arial)
- > 1x BF-3
- > 1x device with an ethernet supported QSFP port

Figure 3-6. RMII NC-SI Diagram

Note: The diagram in Figure 3-6 ignores the physical path from the BMC to the HMC, BMC to the compute motherboard, and BMC to the front I/O board. Also, the interfaces with a 10.20.45.XX IPs are examples. These IPs will differ from setup to setup.

Test Procedure

Step 1: Hardware Configuration

1. Set up two compute trays, each having a BMC, HMC, BF-3, and I/O board.
2. Confirm that the BMCs and HMCs are properly connected.
3. Confirm that the compute tray motherboard to the BF-3 cable is present on both systems.
4. Connect a QSFP cable between the two BF-3s. The QSFP ports will be assigned an IP. This validation guide assumes that the QSFP port closest to the RJ45 port is used on the BF-3. The other ports can be used; the network interface name will be different when assigning the IPs later.
5. Turn on RUN power.
6. For the QSFP ports with a cable installed, confirm their status LEDs are solid green.

Step 2: Connect to the BF-3s on Host OS.

The BF-3 has two hosts:

- > Host OS
- > Host BMC. For testing NC-SI, the Host OS is utilized.

There are two paths for connecting the BF-3 to the Host OS:

- > Through the TH500 Grace CPU
- > Through the BF-3 OOB network interface (RJ45 port).

Use one of the connection methods for executing commands on the BF-3 Host OS.

- > Method 1 – Connect BF-3 Host OS through TH500 Grace CPU

1. SSH to the Grace OS.
2. Output the IPv6 address of the BF-3.

```
ip -6 addr | grep tmfifo_net
```

Example output:

```
7: tmfifo_net0: <BROADCAST,MULTICAST,UP,LOWER_UP> mtu 1500 state UNKNOWN qlen 1000
    inet6 fe80::21a:caff:fe:ff:ff02/64 scope link
```

When two BF-3s are installed, there will be two tmfifo_net interfaces, one for each BF3.

3. Convert the IPv6 address to the address for the Host OS by replacing the last nibble with a '1'. For example:

```
fe80::21a:caff:fe:ff:ff02    fe80::21a:caff:fe:ff:ff01
```

4. From the TH500, SSH to the BF-3 Host OS using the following format:

```
ssh -6 ubuntu@<BF3 Host OS IPv6 address>%<BF3 network interface>
```

Example command:

```
ssh -6 ubuntu@fe80::21a:caff:fe:ff:ff01%tmfifo_net0
```

If you are using the second BF-3, then use tmfifo_net1 as the interface.

- > Method 2 – Connect BF-3 Host OS through OOB interface

1. Take a picture of the BF's part and serial number sticker. Record the MAC address with the label "OOB". This refers to the BF's Host OS.



2. Open a shell from a system on the same subnet as the BF-3. You will need to be able to install nmap on this system. It is recommended to use the TH500's OS.

3. Confirm nmap is installed on the system

```
apt install nmap
```

4. Use the OOB MAC address, and run the following commands

```
MAC='9c:63:c0:7d:21:00' # REPLACE WITH YOUR MAC IN THE SAME FORMAT
NETWORK='ip addr show enP5p9s0 | grep inet | awk '{print $2}''
sudo nmap -sn $NETWORK | grep -iB2 $MAC
```

5. The output should contain the IP address

```
Nmap scan report for 10.20.45.97
Host is up (0.000077s latency).
MAC Address: 9c:63:c0:7d:21:00 (Unknown)
```

6. SSH to this IP address.

Step 3: Network Configuration

1. Connect to the BMC shell and check the status of the NC-SI link:

```
dmesg | grep -I ncsi
```

2. If the output matches the following, reboot the BMC by running reboot, and try the last step again.

```
[ 1.877450] ftgmac100 1e670000.ftgmac: Using NCSI interface
[ 48.578827] ftgmac100 1e670000.ftgmac eth1: NCSI: No channel found to configure!
[ 49.621217] ftgmac100 1e670000.ftgmac eth1: Wrong NCSI state 0x100 in workqueue
```

3. If the output includes the following, it is okay to continue.

```
[ 1.877659] ftgmac100 1e670000.ftgmac: Using NCSI interface
[ 25.683782] ftgmac100 1e670000.ftgmac eth1: NCSI: Handler for packet type 0x82 returned -19
[ 41.289146] ftgmac100 1e670000.ftgmac eth1: NCSI: 'bad' packet ignored for type 0x8b
```

4. Run ifconfig eth1 and confirm that RX and TX packet count are non-zero:

```
root@gb200nvl-bmc:~# ifconfig eth1
eth1      Link encap:Ethernet  HWaddr 02:7A:4E:32:03:A7
```

```

inet addr:169.254.150.148 Bcast:169.254.255.255 Mask:255.255.0.0
inet6 addr: fe80::7a:4eff:fe32:3a7/64 Scope:Link
UP BROADCAST RUNNING MULTICAST MTU:1500 Metric:1
RX packets:82 errors:0 dropped:0 overruns:0 frame:0
TX packets:149 errors:0 dropped:0 overruns:0 carrier:0
collisions:0 txqueuelen:1000
RX bytes:6897 (6.7 KiB) TX bytes:9588 (9.3 KiB)
Interrupt:40

```

- On the first system's BMC, assign the eth1 interface to a new IP on a new network:

```
ifconfig eth1 192.168.1.6 netmask 255.255.255.0
```

- On the second system's BMC, assign the eth1 interface to a new IP on the same network as the previous step:

```
ifconfig eth1 192.168.1.7 netmask 255.255.255.0
```

- On the first system's BF-3's Host OS, assign the interface on the OSFP link with a new IP on the same network as the previous step:

```
sudo ifconfig enp3s0f0s0 192.168.1.2 netmask 255.255.255.0
```

- On the second system's BF-3 Host OS, assign the interface on the QSFP link with a new IP on the same network as the previous step:

```
sudo ifconfig enp3s0f0s0 192.168.1.3 netmask 255.255.255.0
```

These IPs are temporarily configured. If a system is rebooted, then its IP for this setup will be reassigned.

Step 4: Test the links

- On the first BF-3 Host OS, ping the second BMC using the 192.168.1.X network:

```
ping 192.168.1.7
```

- On the second BF-3 Host OS, ping the first BMC using the 192.168.1.X network:

```
ping 192.168.1.6
```

- Both ping commands should output 0% package lost.

Pass or Fail Criteria

Both BF-3s can successfully ping the BMCs successfully with 0% package lost.

3.6.12 RMII NC-SI Electrical Validation

Purpose

Verify the RMII NC-SI interface between the BMC and the BF-3 and NIC meets the electrical specifications of the RMII NC-SI electrical specification. The RMII NC-SI electrical specifications are outlined in the following figures.

Figure 3-7. RMII NC-SI DC Specifications

Parameter	Symbol	Conditions	Minimum	Typical	Maximum	Units
IO reference voltage	$V_{ref}^{[a]}$		3.0	3.3	3.6	V
Signal voltage range	V_{abs}		-0.300		3.765	V
Input low voltage	V_{il}				0.8	V
Input high voltage	V_{ih}		2.0			V
Input high current	I_{ih}	$V_{in} = V_{ref} = V_{ref,max}$	0		200	μA
Input low current	I_{il}	$V_{in} = 0 V$	-20		0	μA
Output low voltage	V_{ol}	$I_{ol} = 4 mA, V_{ref} = min$	0		400	mV
Output high voltage	V_{oh}	$I_{oh} = -4 mA, V_{ref} = min$	2.4		V_{ref}	V
Clock midpoint reference level	V_{ckm}				1.4	V
Leakage current for output signals in high-impedance state	I_z	$0 \leq V_{in} \leq V_{ref}$ at $V_{ref} = V_{ref,max}$	-20		20	μA
<p>^[a] V_{ref} = Bus high reference level (typically the NC-SI logic supply voltage). This parameter replaces the term <i>supply voltage</i> because actual devices may have internal mechanisms that determine the operating reference for the NC-SI that are different from the devices' overall power supply inputs.</p> <p>V_{ref} is a reference point that is used for measuring parameters (such as overshoot and undershoot) and for determining limits on signal levels that are generated by a device. In order to facilitate system implementations, a device shall provide a mechanism (for example, a power supply pin, internal programmable reference, or reference level pin) to allow V_{ref} to be set to within 20 mV of any point in the specified V_{ref} range. This approach enables a system integrator to establish an interoperable V_{ref} level for devices on the NC-SI.</p>						

Figure 3-8. RMII NC-SI AC Specifications




Figure 18 – AC measurements

Table 121 provides AC specifications.

Table 121 – AC specifications


Parameter	Symbol	Minimum	Typical	Maximum	Units
REF_CLK Frequency			50	50+100 ppm	MHz
REF_CLK Duty Cycle		35		65	%
Clock-to-out ^[a] (10 pF ≤ C _{load} ≤ 50 pF)	T _{co}	2.5		12.5	ns
Skew between clocks	T _{skew}			1.5	ns
TXD[1:0], TX_EN, RXD[1:0], CRS_DV, RX_ER, and ARB_IN data setup to REF_CLK rising edge	T _{su}	3			ns
TXD[1:0], TX_EN, RXD[1:0], CRS_DV, RX_ER, and ARB_OUT data hold from REF_CLK rising edge	T _{hd}				ns
Signal Rise/Fall Time	T _r /T _f	0.5		6	ns
REF_CLK Rise/Fall Time	T _{dr} /T _{df}	0.5		3.5	ns
Interface Power-Up High-Impedance Interval	T _{pwz}	2			μs
Power Up Transient Interval (recommendation)	T _{pwt}			100	ns
Power Up Transient Level (recommendation)	V _{pwt}	-200		200	mV
Interface Power-Up Output Enable Interval	T _{pwre}			10	ms
EXT_CLK Startup Interval	T _{clkst}			100	ms

^[a] This timing relates to the output pins, while T_{su} and T_{hd} relate to timing at the input pins.

Test Procedure

1. Set up two compute trays, each having a BMC, HMC, BF-3, and I/O board.
2. Confirm that the BMCs and HMCs are properly connected.

Determine a probing spot for each signal for NC-SI. For example, the NC-SI signals can be identified on the BMC schematics (NVOnline: 1115463 BMC Management Board Design Kit). Partner should check their own BMC designs to identify these signals. Cross-check the layout file for an appropriate test spot.



Signal	Description
REF_CLK	50 MHz clock reference for receive, transmit and control interface
CRS_DV	Carrier sense and receive data validity for the traffic sent from one of the NICs
RXD[1:0]	Receive data (from the NIC to the BMC)
TX_EN	Transmit enable and data validity for the traffic sent from the BMC
TXD[1:0]	Transmit data (from the BMC to the NIC)
RX_ER	Receive error signal, sent from the NIC to the BMC (optional)
ARB_IN	Input data hardware arbitration (optional)
ARB_OUT	Output data hardware arbitration (optional)

3. Submit a rework to add probes to the necessary spots or acquire probe holders for testing the signals.
4. Set up an oscilloscope with the appropriate signals to measure the DC electrical, timing properties of the NC-SI bus and make sure they are within DC and AC specifications.

Pass or Fail Criteria

Ensure the NC-SI waveform captured meets both the DC and AC electrical specifications as outlined.

3.7 Networking I/O Board

This section details the networking I/O board for the NVIDIA GB200 and GB300 NVL72 systems.

3.7.1 CX-7 and CX-8 Mezzanine Network Card Ethernet Validation

This section contains steps to set up and run the I/O stress write test on Ethernet protocol through OSFP medium from the CX-7 and CX-8 ports on the networking I/O board.

Partner is recommended to use the **ib_write_bw** on **Perftest** package tool.

Test Procedure

Following are the steps for Initial setup.

1. Run **mst start**
2. Check **mst status -v**
3. Verify **mlx_0** and **mlx_1** are listed as follows with **mst device 'mt4129'**

```
root@localhost:/home/nvidia# mst status -v
MST modules:
-----
MST PCI module is not loaded
MST PCI configuration module loaded
PCI devices:
-----

```

DEVICE_TYPE	MST	PCI	RDMA	NET	NUMA
BlueField3(rev:1)	/dev/mst/mt41692_pciconf0.1	0006:01:00.1	mlx5_3	net-ibP6s6f1	0
BlueField3(rev:1)	/dev/mst/mt41692_pciconf0	0006:01:00.0	mlx5_2	net-ibP6s6f0	0
ConnectX7(rev:0)	/dev/mst/mt4129_pciconf1	0002:03:00.0	mlx5_1	net-enP2p3s0np0	0
ConnectX7(rev:0)	/dev/mst/mt4129_pciconf0	0000:03:00.0	mlx5_0	net-enP3s0np0	0

Following are the steps for the Ethernet test.

1. Assign ip for **mlx5_0** and **mlx5_1**

```
sudo ifconfig enP2p3s0np0 11.11.11.7 // any arbitrary IP
sudo ifconfig enP3s0np0 11.11.11.8 // any arbitrary IP
```
2. Check **ibstat**, verify port state as “Active;” verify link layer as “Ethernet.”
3. Follow the commands as shown here to start the server and client and verify that the throughput speed is around 740 Gb/s (as highlighted in **green** in the following output).

```
nvidia@localhost:~$ ib_write_bw -d mlx5_0 --report_gbits -b --run_infinitely &
[1] 7860
nvidia@localhost:~$ WARNING: BW peak won't be measured in this run.
```

```
*****
* Waiting for client to connect... *
*****
```

```
nvidia@localhost:~$ ib_write_bw -d mlx5_1 --report_gbits -b --run_infinately 11.11.11.8 &
nvidia@localhost:~$ WARNING: BW peak won't be measured in this run.
```

```
-----
RDMA_Write Bidirectional BW Test
Dual-port      : OFF      Device      : mlx5_0
Number of qps  : 1        Transport type : IB
Connection type : RC      Using SRQ      : OFF
PCIe relax order: ON
-----
```

```
RDMA_Write Bidirectional BW Test
Dual-port      : OFF      Device      : mlx5_1
Number of qps  : 1        Transport type : IB
Connection type : RC      Using SRQ      : OFF
PCIe relax order: ON
ibv_wr* API    : ON
TX depth       : 128
CQ Moderation  : 1
Mtu            : 1024[B]
Link type      : Ethernet
GID index      : 3
Max inline data : 0[B]
rdma_cm QPs    : OFF
Data ex. method : Ethernet
-----
```

```
ibv_wr* API    : ON
TX depth       : 128
CQ Moderation  : 1
Mtu            : 1024[B]
Link type      : Ethernet
GID index      : 3
Max inline data : 0[B]
rdma_cm QPs    : OFF
Data ex. method : Ethernet
-----
```

```
local address: LID 0000 QPN 0x0129 PSN 0x6032f RKey 0x203ebd VAddr 0x00c9bfb01f0000
GID: 00:00:00:00:00:00:00:00:00:00:255:255:11:11:11:07
local address: LID 0000 QPN 0x0129 PSN 0x4b191c RKey 0x203ebd VAddr 0x00b9b586c20000
GID: 00:00:00:00:00:00:00:00:00:00:255:255:11:11:11:08
remote address: LID 0000 QPN 0x0129 PSN 0x6032f RKey 0x203ebd VAddr 0x00c9bfb01f0000
GID: 00:00:00:00:00:00:00:00:00:00:255:255:11:11:11:07
remote address: LID 0000 QPN 0x0129 PSN 0x4b191c RKey 0x203ebd VAddr 0x00b9b586c20000
GID: 00:00:00:00:00:00:00:00:00:00:255:255:11:11:11:08
-----
```

```
-----
#bytes  #iterations  BW peak[Gb/sec]  BW average[Gb/sec]  MsgRate[Mpps]
#bytes  #iterations  BW peak[Gb/sec]  BW average[Gb/sec]  MsgRate[Mpps]
65536   3525074      0.00             739.26              1.410017
65536   3525051      0.00             739.25              1.410008
65536   3525101      0.00             739.26              1.410018
-----
```

65536	3525299	0.00	739.26	1.410018
65536	3525085	0.00	739.26	1.410026
65536	3525086	0.00	739.26	1.410027
65536	3525077	0.00	739.26	1.410029
65536	3525071	0.00	739.25	1.410016
65536	3525072	0.00	739.26	1.410021
65536	3525087	0.00	739.26	1.410029
65536	3525084	0.00	739.25	1.410013
65536	3525085	0.00	739.26	1.410025
65536	3525078	0.00	739.26	1.410025
65536	3525071	0.00	739.25	1.410017
65536	3525075	0.00	739.26	1.410018
65536	3525086	0.00	739.26	1.410028
65536	3525083	0.00	739.26	1.410029
65536	3525085	0.00	739.26	1.410027
65536	3525077	0.00	739.26	1.410018

4. Verify **ispci** speed and width.

```

root@localhost:/home/nvidia# lspci -vvvs 0002:03:00.0 | grep -i "lnk\|dev"
    Status: Cap+ 66MHz- UDF- FastB2B- ParErr- DEVSEL=fast >TAbort- <TAbort- <MAbort- >SERR-
    <PERR- INTx-
        DevCap: MaxPayload 512 bytes, PhantFunc 0, Latency L0s unlimited, L1 unlimited
        DevCtl: CorrErr+ NonFatalErr+ FatalErr+ UnsupReq+
        DevSta: CorrErr- NonFatalErr- FatalErr- UnsupReq- AuxPwr- TransPend-
        LnkCap: Port #0, Speed 32GT/s, Width x16, ASPM not supported
        LnkCtl: ASPM Disabled; RCB 64 bytes, Disabled- CommClk-
        LnkSta: Speed 32GT/s (ok), Width x16 (ok)
        DevCap2: Completion Timeout: Range ABC, TimeoutDis+ NROPrPrP- LTR-
        DevCtl2: Completion Timeout: 50us to 50ms, TimeoutDis- LTR- OBFF Disabled,
        LnkCap2: Supported Link Speeds: 2.5-32GT/s, Crosslink- Retimer+ 2Retimers+ DRS-
        LnkCtl2: Target Link Speed: 32GT/s, EnterCompliance- SpeedDis-
        LnkSta2: Current De-emphasis Level: -6dB, EqualizationComplete+
        EqualizationPhase1+
        VF offset: 1, stride: 1, Device ID: 101e
        LnkCtl3: LnkEquInterruptEn- PerformEqu-
root@localhost:/home/nvidia# lspci -vvvs 0000:03:00.0 | grep -i "lnk\|dev"
    Status: Cap+ 66MHz- UDF- FastB2B- ParErr- DEVSEL=fast >TAbort- <TAbort- <MAbort- >SERR-
    <PERR- INTx-
        DevCap: MaxPayload 512 bytes, PhantFunc 0, Latency L0s unlimited, L1 unlimited
        DevCtl: CorrErr+ NonFatalErr+ FatalErr+ UnsupReq+
        DevSta: CorrErr- NonFatalErr- FatalErr- UnsupReq- AuxPwr- TransPend-
        LnkCap: Port #0, Speed 32GT/s, Width x16, ASPM not supported
        LnkCtl: ASPM Disabled; RCB 64 bytes, Disabled- CommClk-
        LnkSta: Speed 32GT/s (ok), Width x16 (ok)
        DevCap2: Completion Timeout: Range ABC, TimeoutDis+ NROPrPrP- LTR-
        DevCtl2: Completion Timeout: 50us to 50ms, TimeoutDis- LTR- OBFF Disabled,
        LnkCap2: Supported Link Speeds: 2.5-32GT/s, Crosslink- Retimer+ 2Retimers+ DRS-
        LnkCtl2: Target Link Speed: 32GT/s, EnterCompliance- SpeedDis-
        LnkSta2: Current De-emphasis Level: -6dB, EqualizationComplete+
        EqualizationPhase1+

```

```
VF offset: 1, stride: 1, Device ID: 101e
LnkCtl3: LnkEquInterruptEn- PerformEqu-
```

5. Verify that there is no system error messages by dmesg.
6. Verify temperature sensors are reporting properly on the CX-7 and CX-8 I/O board.

```
nvidia@localhost:~$ sensors|grep -i mlx5 -A2
mlx5-pci-60100
Adapter: PCI adapter
asic:          +56.0°C (crit = +105.0°C, highest = +57.0°C)
--
mlx5-pci-0300
Adapter: PCI adapter
asic:          +48.0°C (crit = +105.0°C, highest = +51.0°C)
--
mlx5-pci-60101
Adapter: PCI adapter
asic:          +56.0°C (crit = +105.0°C, highest = +57.0°C)
--
mlx5-pci-20300
Adapter: PCI adapter
asic:          +49.0°C (crit = +105.0°C, highest = +52.0°C)
```

7. Verify MLXLink on PCIe and cable for FOM and Error checks.

```
nvidia@localhost:~$ sudo mlxlink -d /dev/mst/mt4129_pciconf0 -c -e -m

Operational Info
-----
State                : Active
Physical state       : LinkUp
Speed                : 400G
Width                : 4x
FEC                  : Standard_RS-FEC - (544,514)
Loopback Mode        : No Loopback
Auto Negotiation     : ON

Supported Info
-----
Enabled Link Speed (Ext.) : 0x0001bff2
(400G_4X,400G_8X,200G_2X,200G_4X,100G_1X,100G_2X,100G_4X,50G_1X,50G_2X,40G,25G,10G,1G)
Supported Cable Speed (Ext.) : 0x0009bffe
(800G_8X,400G_4X,400G_8X,200G_2X,200G_4X,100G_1X,100G_2X,100G_4X,50G_1X,50G_2X,40G,25G,10G,5G,2
.5G,1G)

Troubleshooting Info
-----
Status Opcode          : 0
Group Opcode           : N/A
Recommendation          : No issue was observed.
Time to Link Up        : 0.360 sec

Tool Information
```

```

-----
Firmware Version           : 28.98.9122
amBER Version              : 3.2
MFT Version                 : mft 4.28.0-97

Physical Counters and BER Info
-----
Time Since Last Clear [Min] : 12.4
Effective Physical Errors    : 0
Effective Physical BER       : 15E-255
Raw Physical Errors Per Lane : 475,871,1009,774
Raw Physical BER Per Lane   : 2E-11,4E-11,5E-11,4E-11
Link Down Counter           : 0
Link Error Recovery Counter : 0
Raw Physical BER            : 1E-11

EYE Opening Info
-----
FOM Mode                   : SLRG_FOM_MODE_EYEO
Lane                       :      0,      1,      2,      3
Initial FOM                :    109,    102,    99,    101
Last FOM                   :    102,    108,    105,    108
Upper Grades               :    102,    104,    104,    106
Mid Grades                 :    123,    119,    116,    123
Lower Grades               :    103,    102,    104,    105

Module Info
-----
Identifier                  : OSFP
Compliance                  : 800G-ETC-CR8 or 800GBASE-CR8
Cable Technology            : Copper cable unequalized
Cable Type                  : Passive copper cable
OUI                         : Other
Vendor Name                 : Amphenol
Vendor Part Number         : NNDDDA-0006
Vendor Serial Number       : APF243700691DN
Rev                         : 1
Wavelength [nm]            : N/A
Transfer Distance [m]       : 0.5
Attenuation (5g,7g,12g,25g) [dB] : 3,4,6,12
FW Version                  : N/A
Digital Diagnostic Monitoring : No
Power Class                 : N/A
CDR RX                     : N/A
CDR TX                     : N/A
LOS Alarm                   : N/A
Temperature [C]            : N/A
Voltage [mV]               : N/A
Bias Current [mA]          : N/A

```

```

Rx Power Current [dBm]           : N/A
Tx Power Current [dBm]           : N/A
Intra-ASIC Latency [ns]          : N/A
Module Datapath Latency [ns]     : N/A
Round Trip Latency [ns]          : N/A
SNR Media Lanes [dB]             : N/A
SNR Host Lanes [dB]              : N/A
IB Cable Width                   : 1x,2x,4x,8x
Memory Map Revision              : 81
Linear Direct Drive              : 0
Cable Breakout                   : OSFP to OSFP
SMF Length                       : N/A
MAX Power                        : 1
Cable Rx AMP                     : N/A
Cable Rx Emphasis (Pre)          : N/A
Cable Rx Post Emphasis           : N/A
Cable Tx Equalization            : N/A
Wavelength Tolerance             : N/A
Module State                     : N/A
DataPath state [per lane]        : N/A
Rx Output Valid [per lane]       : N/A
Nominal bit rate                 : N/A
Rx Power Type                    : OMA
Manufacturing Date               : 21_09_24
Active Set Host Compliance Code   : 800G-ETC-CR8 or 800GBASE-CR8
Active Set Media Compliance Code  : N/A
Error Code Response              : ConfigUndefined
Module FW Fault                  : N/A
DataPath FW Fault                : N/A
Tx Fault [per lane]              : N/A
Tx LOS [per lane]                : N/A
Tx CDR LOL [per lane]            : N/A
Rx LOS [per lane]                : N/A
Rx CDR LOL [per lane]            : N/A
Tx Adaptive EQ Fault [per lane]  : N/A

```

```
nvidia@localhost:~$ sudo mlxlink -d /dev/mst/mt4129_pciconf1 -c -e -m
```

Operational Info

```
-----
```

```

State                           : Active
Physical state                   : LinkUp
Speed                           : 400G
Width                           : 4x
FEC                             : Standard_RS-FEC - (544,514)
Loopback Mode                   : No Loopback
Auto Negotiation                : ON

```

Supported Info

```

-----
Enabled Link Speed (Ext.)      : 0x0001bff2
(400G_4X,400G_8X,200G_2X,200G_4X,100G_1X,100G_2X,100G_4X,50G_1X,50G_2X,40G,25G,10G,1G)
Supported Cable Speed (Ext.)   : 0x0009bffe
(800G_8X,400G_4X,400G_8X,200G_2X,200G_4X,100G_1X,100G_2X,100G_4X,50G_1X,50G_2X,40G,25G,10G,5G,2
.5G,1G)

Troubleshooting Info
-----
Status Opcode                  : 0
Group Opcode                   : N/A
Recommendation                 : No issue was observed.
Time to Link Up                : 0.365 sec

Tool Information
-----
Firmware Version               : 28.98.9122
amBER Version                  : 3.2
MFT Version                    : mft 4.28.0-97

Physical Counters and BER Info
-----
Time Since Last Clear [Min]    : 12.5
Effective Physical Errors       : 0
Effective Physical BER          : 15E-255
Raw Physical Errors Per Lane    : 1233,1773,871,726
Raw Physical BER Per Lane      : 6E-11,1E-10,4E-11,4E-11
Link Down Counter              : 0
Link Error Recovery Counter     : 0
Raw Physical BER               : 1E-11

EYE Opening Info
-----
FOM Mode                       : SLRG_FOM_MODE_EYEO
Lane                           :      0,      1,      2,      3
Initial FOM                    :    103,    102,    93,    105
Last FOM                       :    107,     98,   107,   104
Upper Grades                   :    103,     97,   105,   100
Mid Grades                     :    117,    108,   109,   115
Lower Grades                   :    106,    100,   101,   108

Module Info
-----
Identifier                     : OSFP
Compliance                     : 800G-ETC-CR8 or 800GBASE-CR8
Cable Technology                : Copper cable unequalized
Cable Type                     : Passive copper cable
OUI                             : Other
Vendor Name                    : Amphenol
Vendor Part Number             : NNDDDA-0006

```

Vendor Serial Number : APF243700691DN
 Rev : 1
 Wavelength [nm] : N/A
 Transfer Distance [m] : 0.5
 Attenuation (5g,7g,12g,25g) [dB] : 3,4,6,12
 FW Version : N/A
 Digital Diagnostic Monitoring : No
 Power Class : N/A
 CDR RX : N/A
 CDR TX : N/A
 LOS Alarm : N/A
 Temperature [C] : N/A
 Voltage [mV] : N/A
 Bias Current [mA] : N/A
 Rx Power Current [dBm] : N/A
 Tx Power Current [dBm] : N/A
 Intra-ASIC Latency [ns] : N/A
 Module Datapath Latency [ns] : N/A
 Round Trip Latency [ns] : N/A
 SNR Media Lanes [dB] : N/A
 SNR Host Lanes [dB] : N/A
 IB Cable Width : 1x,2x,4x,8x
 Memory Map Revision : 81
 Linear Direct Drive : 0
 Cable Breakout : QSFP to QSFP
 SMF Length : N/A
 MAX Power : 1
 Cable Rx AMP : N/A
 Cable Rx Emphasis (Pre) : N/A
 Cable Rx Post Emphasis : N/A
 Cable Tx Equalization : N/A
 Wavelength Tolerance : N/A
 Module State : N/A
 DataPath state [per lane] : N/A
 Rx Output Valid [per lane] : N/A
 Nominal bit rate : N/A
 Rx Power Type : OMA
 Manufacturing Date : 21_09_24
 Active Set Host Compliance Code : 800G-ETC-CR8 or 800GBASE-CR8
 Active Set Media Compliance Code : N/A
 Error Code Response : ConfigUndefined
 Module FW Fault : N/A
 DataPath FW Fault : N/A
 Tx Fault [per lane] : N/A
 Tx LOS [per lane] : N/A
 Tx CDR LOL [per lane] : N/A
 Rx LOS [per lane] : N/A
 Rx CDR LOL [per lane] : N/A
 Tx Adaptive EQ Fault [per lane] : N/A

Pass or Fail Criteria

Ensure Ethernet link throughput, error, and temperature sensors are all within the expected range.

3.7.2 CX-7 and CX-8 Mezzanine Network Card I/O Board InfiniBand Validation

Purpose

This section contains steps to set up and run the I/O stress write test on InfiniBand protocol through OSFP medium from the CX-7 and CX-8 ports on the networking I/O board.

Partner is recommended to use the **ib_write_bw** on **Perftest** package tool.

Test Procedure

Following are the steps for Initial setup.

1. Run **mst start**
2. Check **mst status -v**
3. Verify **mlx_0** and **mlx_1** are listed as follows with **mst device 'mt4129'**

Following the steps for the InfiniBand test.

1. Check **ibstat**, verify port state as “Active;” verify link layer as “InfiniBand.”
2. Assign IP for **mlx5_0** and **mlx5_1**

```
sudo ifconfig ibp3s0 11.11.11.7 // any arbitrary IP
sudo ifconfig ibP2p3s0 11.11.11.8 // any arbitrary IP
```

3. Arm and activate the ports.

```
sudo ibportstate -C mlx5_0 -P 1 -D 0 1 arm;
sudo ibportstate -C mlx5_1 -P 1 -D 0 1 arm;
sudo ibportstate -C mlx5_1 -P 1 -D 0 1 active;
sudo ibportstate -C mlx5_0 -P 1 -D 0 1 active
```

4. Port GUID and OpenSM step.

```
opensm -g <guid>
```

5. Check **mst status -v** for InfiniBand ports.

```
root@localhost:/home/nvidia# mst status -v
MST modules:
-----
MST PCI module is not loaded
MST PCI configuration module loaded
PCI devices:
-----
DEVICE_TYPE      MST                                PCI          RDMA          NET              NUMA
BlueField3(rev:1) /dev/mst/mt41692_pciconf0.1 0006:01:00.1  mlx5_3        net-ibP6s6f1     0
BlueField3(rev:1) /dev/mst/mt41692_pciconf0 0006:01:00.0  mlx5_2        net-ibP6s6f0     0
ConnectX7(rev:0)  /dev/mst/mt4129_pciconf1 0002:03:00.0  mlx5_1        net-ibP2p3s0     0
ConnectX7(rev:0)  /dev/mst/mt4129_pciconf0 0008:03:00.0  mlx5_0        net-ibp3s0       0
```

6. Use the **ib_write** command to verify the throughput on **mlx5_0**.

```
ib_write_bw' -d mlx5_0 -p 11000 -F -report_gbits -D 3 -b --run_infinitely 11.11.11.7 &
```

```
root@localhost:/home/nvidia# ib_write_bw -d mlx5_0 -p 11000 -F --report_gbits -D 3 -b --run_infinitely 11.11.11.7
WARNING: BW peak won't be measured in this run.

=====
RDMA_write Bidirectional BW Test
Dual-port      : OFF          Device      : mlx5_0
Number of qps  : 1           Transport type : IB
Connection type: RC          Using SRQ     : OFF
PCIe relax order: ON
ibv_wrr API    : ON
TX depth       : 128
CQ Moderation  : 1
MRU            : 4096[0]
Link type      : IB
Max inline data: 0[0]
rdma_cm QPs    : OFF
Data ex. method: Ethernet
=====

local address: LID 0x01 QPN 0x0047 PSN 0xc2860a RKey 0x1ffffb VAddr 0x00c8e675b00000
remote address: LID 0x02 QPN 0x0047 PSN 0x3f053e RKey 0x1ffffb VAddr 0x00bbe0dc900000
=====
```

#bytes	#iterations	BW peak[Gb/sec]	BW average[Gb/sec]	MaxRate[Mbps]
65536	2211987	0.00	773.13	1.474626
65536	2212022	0.00	773.14	1.474653
65536	2212017	0.00	773.14	1.474665
65536	2212017	0.00	773.15	1.474662
65536	2212068	0.00	773.14	1.474652
65536	2212033	0.00	773.15	1.474667
65536	2212015	0.00	773.15	1.474663
65536	2212026	0.00	773.15	1.474668
65536	2212028	0.00	773.16	1.474676
65536	2212060	0.00	773.17	1.474699
65536	2212031	0.00	773.15	1.474673
65536	2211979	0.00	773.13	1.474633
65536	2212011	0.00	773.14	1.474644
65536	2212020	0.00	773.15	1.474660
65536	2211979	0.00	773.14	1.474642
65536	2211976	0.00	773.14	1.474641
65536	2211983	0.00	773.13	1.474632
65536	2212179	0.00	773.20	1.474759
65536	2212163	0.00	773.20	1.474767
65536	2212175	0.00	773.20	1.474759
65536	2212176	0.00	773.20	1.474761
65536	2212131	0.00	773.19	1.474739
65536	2212066	0.00	773.17	1.474784
65536	2212179	0.00	773.21	1.474778
65536	2212178	0.00	773.20	1.474758
65536	2212173	0.00	773.20	1.474758
65536	2212163	0.00	773.19	1.474748

7. Use the **ib_write** command to verify the throughput on **mlx5_1**.

```
ib_write_bw -d mlx5_1 -p 11000 -F -report_gbits -D 3 -b -run_infinitely &
```

```
root@localhost:/home/nvidia# ib_write_bw -d mlx5_1 -p 11000 -F --report_gbits -D 3 -b --run_infinitely &
[1] 4924
root@localhost:/home/nvidia# WARNING: BW peak won't be measured in this run.

*****
+ Waiting for client to connect... +
*****

-----
RDMA_Write Bidirectional BW Test
Dual-port      : OFF          Device      : mlx5_1
Number of ops   : 1           Transport type : IB
Connection type : RC          Using SRQ    : OFF
PCIe relax order: ON
ibv_wr API      : ON
TX depth       : 128
CQ Moderation   : 1
MTU            : 4096[B]
Link type       : IB
Max inline data : 0[B]
rdma_cm QPs     : OFF
Data ex. method : Ethernet

-----
local address: LID 0x02 QPN 0x0047 PSN 0x3f953e RKey 0x1ffffb VAddr 0x00bbe0dc9b0000
remote address: LID 0x01 QPN 0x0047 PSN 0xc3840a RKey 0x1ffffb VAddr 0x00c0e475b00000

-----
#bytes    #iterations    BW peak[Gb/sec]    BW average[Gb/sec]    MsgRate[Mpps]
65536     2211907           0.00              773.13                1.474625
65536     2212016           0.00              773.14                1.474639
65536     2212018           0.00              773.14                1.474658
65536     2212018           0.00              773.15                1.474659
65536     2212011           0.00              773.15                1.474664
65536     2212039           0.00              773.15                1.474663
65536     2212016           0.00              773.15                1.474665
65536     2212034           0.00              773.15                1.474669
65536     2212017           0.00              773.15                1.474668
65536     2212078           0.00              773.17                1.474709
65536     2212047           0.00              773.15                1.474669
65536     2211981           0.00              773.13                1.474623
65536     2212014           0.00              773.15                1.474661
65536     2212017           0.00              773.15                1.474678
65536     2211989           0.00              773.14                1.474645
65536     2211997           0.00              773.14                1.474655
65536     2212007           0.00              773.14                1.474655
65536     2212177           0.00              773.20                1.474767
65536     2212168           0.00              773.20                1.474759
65536     2212174           0.00              773.20                1.474764
65536     2212179           0.00              773.20                1.474778
65536     2212141           0.00              773.19                1.474748
65536     2212095           0.00              773.17                1.474788
```

8. Verify **lspci** speed and with through the same command under the Ethernet test section:

```
/home/nvidia# lspci -vvvs 0002:03:00.0 | grep -i "lnk\|dev"
/home/nvidia# lspci -vvvs 0000:03:00.0 | grep -i "lnk\|dev"
```

9. Verify the temperature sensors through the same command under the Ethernet test section:

```
sensors|grep -i mlx5 -A2
```

10. Verify **MLXLink** on PCIe and cable for FOM and error checks through the same command under the Ethernet test section:

```
sudo mlxlink -d /dev/mst/mt4129_pciconf0 -c -e -m
sudo mlxlink -d /dev/mst/mt4129_pciconf1 -c -e -m
```

Pass or Fail Criteria

Ensure InfiniBand link throughput, error, and temperature sensors are all within the expected range.

3.8 BMC

This section details the BMC hardware testing and procedures for the GB200 and GB300 NVL systems.

3.8.1 BMC FRU Write

Purpose

Verify the BMC can access FRU EEPROM information in the Bianca compute tray.

Test Procedure

Use the following steps to program and verify that FRU write is successful.

1. Copy the <fru.bin> file to the BMC root directly via SSH or SFTP
2. Replace <fru.bin> with your fru bin file you want to program
3. Replace <i2c_bus_nr> with the I2C bus number the FRU you want to program is on. See Table 3-9 for the I2C address and I2C bus number.
4. Replace <i2c_addr> with the I2C address number of the FRU you want to program. See for the I2C address and I2C bus number.
5. Write the EEPROM contents with the following command:

```
dd if=<fru.bin> of=/sys/class/i2c-dev/i2c-<i2c_bus_nr>/device/2-00<i2c_addr>/eeprom
```

6. Verify that the write was successful with the command:

```
i2cdump -f -y <i2c_bus_nr> <i2c_addr>
```

Table 3-9. List of FRU EEPROMs in GB200 and GB300 Bianca Compute Tray

#	FRU Name	Device	I2C Logical Bus (BMC)	I2C Address	Device Type
1	Bianca Board1 NVLink Cable3 FRU	AT24C02C	1	0x55	24c02
2	Bianca Board1 NVLink Cable2 FRU	AT24C02C	1	0x54	24c02
3	Bianca Board1 FRU	24AA64	1	0x50	24c64
4	HMC FRU	AT24C02D	2	0x57	24c02
5	Bianca Board0 NVLink Cable1 FRU	AT24C02C	2	0x55	24c02
6	Bianca Board0 NVLink Cable0 FRU	AT24C02C	2	0x54	24c02
7	Bianca Board0 FRU	24AA64	2	0x50	24c64
8	PDB FRU	M24C02	6	0x50	24c02
9	Bianca DC-SCM_1 FRU	24AA64	9	0x50	24c64
10	Bianca DC-SCM_0 FRU	24AA64	9	0x51	24c64

#	FRU Name	Device	I2C Logical Bus (BMC)	I2C Address	Device Type
11	BMC FRU	CAT34C02	10	0x50	24c02
12	IPEX Bridge 0 FRU	M24128	14	0x55	24c128
13	E1.s Backplane 0 FRU	M24128	14	0x56	24c128
14	BF3 Board0 FRU	BR24G128NXX	14	0x50	24c128
15	IPEX Bridge 1 FRU	M24128	15	0x55	24c128
16	E1.s Backplane 1 FRU	M24128	15	0x56	24c128
17	BF3 Board1 FRU	BR24G128NXX	15	0x50	24c128
18	OSFP Board0 FRU	M24128	21	0x52	24c128
19	CX7 IO Board0 FRU	P24C04C	21	0x50	24c64
20	Front IO FRU	M24128	23	0x57	24c128
21	1G NIC FRU	M24128	25	0x51	24c128
22	OSFP Board1 FRU	M24128	33	0x52	24c128
23	CX7 IO Board1 FRU	P24C04C	33	0x50	24c64

Pass or Fail Criteria

Verify that BMC has access to and can write all the FRU information

3.8.2 BMC Power Control (STANDBY, RUN, AUX)

Purpose

Verify the BMC firmware can control power to the compute tray. Partners must implement those power features to allow for Standby power, RUN power, and AUX power cycle.

Test Procedure

Following are the three different methods of power cycling the Bianca compute tray:

- > AUX power cycle (or AC power cycle for compute tray) is executed through the BMC AUX command to the PDB (power distribution board). The PDB will turn off power to the Bianca compute boards, cutting power to both RUN power (**12V_RUN**) and Standby power (**12V_STBY**). For example, from the BMC run the following:

```
stbypowerctrl.sh aux_cycle
```

- > DC power cycle is executed through the BMC to turn on or off only the RUN power (**12V_RUN**). For example, from the BMC run the following commands:

```
powerctrl.sh power_on      #Turn on RUN power
powerctrl.sh power_off     #Turn off RUN power
powerctrl.sh power_status  #Getting RUN power status
powerctrl.sh power_cycle   #DC power cycle
```

- > Standby power control is executed through the BMC to turn on or off the STBY power (**12V_STBY**). For example, from the BMC run the following commands:

```
stbypowerctrl.sh power_on      #Turn on STBY power
stbypowerctrl.sh power_off     #Turn off STBY power
stbypowerctrl.sh power_status  #Getting STBY power status
```



Note: Depending on the BMC firmware implementation, partners may need to modify the commands to execute the RUN, STBY, and AUX power control.

Pass or Fail Criteria

- > Verify that the BMC commands are implemented correctly, and when executed, the compute tray STANDBY and RUN power can be controlled according to the commands.
- > Verify that the BMC can successfully execute an AUX power cycle.

3.9 System

This section details the system testing and procedures for the GB200 and GB300 NVL systems.

3.9.1 System Reboot and Power Cycle Stress Testing

Purpose

This test ensures that the quality of the GB200 and GB300 NVL72 compute trays do not deviate from their expected behavior across different modes of power reboot. Refer to Section 3.7.2 “BMC Power Control (STANDBY, RUN, AUX)” on BMC controlled power cycling.

Prerequisites

Ensure test capabilities for logging the dmesg and lspci outputs across each reboot cycle to detect if the output is faulty.

Test Procedure

1. Perform AC power cycles on the GB200 and GB300 NVL72 compute trays
 - a. Ensure all PCIe devices seen on the host system are enumerated with the expected speed and width using lspci. Here are examples of PCIe devices to check: GPU, CX-7, CX-8, BF-3, SSD, PCIe Switch, 1G NIC, and so on.
 - b. Check dmesg for any unexpected PCIe AER errors
 - c. Check if the full power sequencing has completed
 - d. Check if all I2C end points are on bus using I2C scan
 - e. Check if USB path from HMC to BMC is up

2. Perform DC power cycles on the Bianca compute trays.
 - a. Ensure all PCIe devices seen on the host system are enumerated with the expected speed and width using lspci. Here are examples of PCIe devices to check: GPU, CX-7, BF-3, SSD, PCIe Switch, 1G NIC, and so on.
 - b. Check dmesg for any unexpected PCIe AER errors
 - c. Check if the full power sequencing has completed.
 - d. Check if all I2C end points are on bus using I2C scan
 - e. Check if USB path from HMC to BMC is up
3. Perform Warm Reboot power cycles on the Bianca compute trays.
 - a. Ensure all PCIe devices seen on the host system are enumerated with the expected speed and width using lspci. Here are examples of PCIe devices to check: GPU, CX-7, BF-3, SSD, PCIe Switch, 1G NIC, and so on.
 - b. Check dmesg for any unexpected PCIe AER errors
 - c. Check if the full power sequencing has completed
 - d. Check if all I2C end points are on bus using I2C scan
 - e. Check if USB path from HMC to BMC is up

Pass or Fail Criteria

- > For each AC cycle, there are no issues with PCIe, InfiniBand, power sequencing, I2C bus scan, and USB checks.
- > For each DC cycle, there are no issues with PCIe, InfiniBand, power sequencing, I2C bus scan, and USB checks.
- > For each Warm Reboot cycle, there are no issues with PCIe, InfiniBand, power sequencing, I2C bus scan, and USB checks.

3.9.2 Wide Area Test

Purpose

The wide area test (WAT) test is a series of 24-hour stress tests for the fully assembled compute tray. WAT test typically is done on multiple units to ensure that the hardware functions when scaled to a larger number of units.

Prerequisites

WAT test should be done on full-featured enabled hardware samples. This means full-featured firmware and a fully populated compute tray. Firmware does not need to be optimized for this test.

Test Procedure

Partners can utilize the NVQual package and Partner Manufacturing Diag and select the corresponding tests and loop for 24 hours.

Refer to the *NVQual User's Guide* (NVOnline: 1119931) for instructions on creating test loops to create WAT testing.

Table 3-10. Compute Tray WAT

ID	Subcategory	Test Item Description	Expected Results
SY.14	Tray CLink WAT	Run multiple loops of NVQual CLink test for 24 hours (NVQual Test #8)	Compute tray passes without errors
SY.15	Tray NVLink WAT	Run multiple loops of NVQual NVLink test for 24 hours (NVQual Test #9)	Compute tray passes without errors
SY.16	Tray PCIe WAT	Run multiple loops of NVQual PCIe tests for 24 hours (NVQual Test #16 - #21)	Compute tray passes without errors
SY.17	Tray Thermal/Power WAT	Do extended continues thermal/power stress for 24 hours (Run power/thermal stress test continuously). Stress at module max spec.	Compute tray passes without errors

Pass or Fail Criteria

For each of the WAT tests, partners should check the NVQual tests passed without fail. Partners are not required to submit the WAT test logs back to NVIDIA.

3.9.3 Reboot WAT

Purpose

The wide-area test (WAT) test is a series of 24-hour stress tests to for the fully assembled compute tray. WAT test typically is done on multiple units to ensure that the hardware functions when scaled to a larger number of units.

Prerequisites

WAT test should be done on full-featured enabled hardware samples. This means full-featured firmware and a fully populated compute tray. Firmware does not need to be optimized for this test.

Test Procedure

Partners should perform each of the reboot stress tests for 1000x cycles to ensure that their system can reliably reboot upon every cycle.

Table 3-11. Reboot WAT

ID	Subcategory	Test Item Description	Expected Results
SY.14	Warm reboot stress test	1000x Warm reboots, check for reliable power control and ensure OS, PCIe, MCTP, SSIF and FPGA stability each cycle	Ensure reliable OS boot and constant PCIe and MCTP enumeration and FPGA stability
SY.15	AC reboot stress test	1000x AC cycles by completely removing power from tray, check for reliable power control and ensure OS,	Ensure reliable OS boot and constant PCIe and MCTP

ID	Subcategory	Test Item Description	Expected Results
		PCIe, MCTP, SSIF and FPGA stability each cycle	enumeration and FPGA stability
SY.16	DC reboot stress test	1000x DC cycles (run power and standby power from BMC), check for reliable power control and ensure OS, PCIe, MCTP, SSIF and FPGA stability each cycle	Ensure reliable OS boot and constant PCIe and MCTP enumeration and FPGA stability

3.9.4 L10 Partner Diagnostics WAT

Purpose

WAT test typically is done on multiple units to ensure that the hardware functions when scaled to a larger number of units.

Ensure the compute tray function and performance by running through an extended loop test of the L10 partner diagnostics for the compute tray.

Prerequisites

Partners must use the latest test fixtures and loopback cables for CX-7, CX-8, and BF-3 as listed on the *GB200 NVL72 Manufacturing Product Engineering and Test Playbook* (NVOnline: 1123054) and the *GB300 NVL72 Mfg Product Engg Test Playbook* (NVOnline: 1131118).

Table 3-12. BF-3, CX-7, CX-8, NVLink, Loopback Cable, and Test Cage

Item	Supplier	Part Number
BF-3 Loopback cable ¹	Amphenol	NAAAFQ-N906 (0.5 m)
CX-7 Loopback cable ²	NVIDIA Amphenol	MCP4Y10-N00A-FLT NALLFQ-N906 (0.5 m)
CX-8 Loopback cable	Amphenol	NALLG3-N906
Test cage (Mini cable cartridge)	EPD5	1A724D100-600-G
NVLink Loopback cable	Amphenol	HS32838-001

Notes:

¹NAAAFQ-N906: 0.5m, QSFP 112G PAM4, 32 AWG cable with FRU EEPROM for IB and Ethernet in CMIS format, compatible with BF3 QSFP Ports.

²NALLFQ-N906: 0.5m, OSFP RHS-RHS, 112G PAM4, 32 AWG cable with FRU EEPROM for IB and Ethernet in CMIS format, compatible with CX-7 I/O.

Test Procedure

1. Set up the CX-7, CX-8, and BF-3 loopback cables as outlined in the *GB200 and GB300 NVL72 Manufacturing Product Engineering and Test Playbook* (NVOnline: 1123054, and 1131118).
 - a. Follow the recommended cabling to minimize cable stress on the OSFP contact and interference between MTF (manufacturing test fixture) slots.
2. Run through the L10 Partner Diagnostics 10x times and ensure that their system passes every iteration of the partner diagnostics.

Pass or Fail Criteria

All iterations of the L10 partner diagnostics passes.

3.10 Environmental, Reliability, and Electromagnetic Compatibility

NVIDIA recognizes the diversity of potential use cases that system partners may encounter. The following test lists are guidance from NVIDIA for the areas concerning environmental factors, reliability, and robustness.

Partners are recommended to modify and or conduct additional testing that may be necessary for their specific use case and ensure that all potential scenarios are addressed appropriately.

3.10.1 L10 Package Testing

Purpose

The purpose of performing package testing is to ensure that the packaged compute tray can withstand the physical stress it may encounter during transportation, storage, and handling.

Test Procedure

Partners should test to the industrial test standards of ISTA. Perform the test items in the following table using the test conditions highlighted in the “Test Item Description” column.

Table 3-13. L10 Packaging Test Summary

ID	Subcategory	Test Item Description	Test Procedure
PK.1	Package/Product Visual Inspection and Product Functional PRE-Test	Run functional test on the product using the latest manufacturing diagnostic. Perform visual inspection and record all noted cosmetic observations	Visual inspection and MFG Diagnostics

ID	Subcategory	Test Item Description	Test Procedure
PK.2	Atmospheric Pre-Conditioning	Packaged product shall be preconditioned to laboratory ambient temperature and humidity for minimum of 12 hours	ISTA 3B, Block #1
PK.3	Atmospheric Conditioning (Required only for non rigid containers)	[Hot, Humid] then [Extreme Heat, Moderate RH] [38°C, 85% RH for 72 hours] then [60°C, 30% RH for 6 hours]	ISTA 3B, Block #1
PK.4	Tip Test	Test up to 22-degree angle, without letting fall. Report on center of gravity tilt angle. If packaged product fail this test, DO NOT let it fall to the floor. Gently return the product to upright position and note failure. Continue testing.	ISTA 3B, Block #2
PK.5	Shock – Rotational Drop	Drop height 6 in (150 mm) for packaged products weighing 500 lb (230 Kg) or more	ISTA 3B, Block #5
PK.6	Shock – Incline or Horizontal Impact	Impact velocity 48 in/sec (1.2 m/sec) minimum or 3 in (76 mm) drops	ISTA 3B, Block #6
PK.7	Truck Vibration - Random with top load	Overall 0.54 Grms, 120 minutes	ISTA 3B, Block #9
PK.8	Air Vibration - Random	Combination of High (0.29Grms), Medium (0.22 Grms) and Low (0.16 Grms) air profile; 120 minutes	ASTM D4169-23, section 12.4.2.2
PK.9	Concentrated Impact (Required only for non rigid containers)	Free-fall, or guided fall drop	ISTA 3B, Block #10
PK.10	Fork Lift Handling (Required only for non rigid containers)	Flat Push and Rotate Tests, Elevated Push and Pull Tests, Elevated Rotate Tests, Load stability test over a handling course.	ISTA 3B, Block #15
PK.11	Shock – Rotational Drop	Drop height 6 in (150 mm) for packaged products weighing 500 lb (230 Kg) or more	ISTA 3B, Block #13
PK.12	Shock – Incline or Horizontal Impact	Impact velocity 48 in/sec (1.2 m/sec) minimum or 3 in (76 mm) drops	ISTA 3B, Block #14
PK.13	Package/Product Visual Inspection and Product Functional POST-Test	Run functional test on the product using the latest manufacturing diagnostic. Perform visual inspection and record all noted cosmetic observations	Visual inspection and MFG Diagnostics

Pass or Fail Criteria

Test items in Table 3-13 are completed and passed. The product did not sustain any damage.

- > Product is damage-free; no structural damage including no detached, loose, fractured, or deformed material part(s)
- > Product cosmetic areas are not degraded beyond manufacturing or final acceptance criteria. Cosmetic damage is any abnormality that makes the product unacceptable to the customer.
- > No conductive particles (wire, connectors, and so on) should be exposed because of the testing.
- > The product should meet all manufacturing specifications and tolerances after testing
- > All product electrical and software functions perform to specification

3.10.2 Shock and Vibration Test

Purpose

The purpose of shock and vibration testing is to ensure that the compute tray can withstand physical stress during transportation, handling, and operation. The testing simulates the effects of sudden impacts and continuous or repetitive movements to verify the compute tray's durability and functionality.

Test Procedure

Perform the test items in the following table using the test conditions highlighted in the "Test Item Description" column.

Table 3-14. Shock and Vibration Test Summary

ID	Subcategory	Test Item Description	Expected Results
SV.1	Vibration Random (Operating)	Freq (Hz) / PSD level (G ² /Hz) / Slope (dB/Oct) 5-10 / - / +12 10-50 / 0.0002 / - 50-100 / - / -12 nominal of 0.1 Grms (X, Y, Z) 30 min/axis / OF	No permanent system damage, no parts or connectors dislodged and the system stays operational.
SV.2	Vibration Sinusoidal (Operating)	5-500-5 Hz, 1.0 oct/min 0.1G, one sweep/axis, (Z) only 1 sweep / OF	No permanent system damage, no parts or connectors dislodged and the system stays operational.
SV.3	Vibration Random (Non-Operating)	Freq (Hz) / PSD level (G ² /Hz) / Slope (dB/Oct) 0.0002 G ² /Hz at 2 Hz	No permanent system damage and no parts or connectors dislodged.

ID	Subcategory	Test Item Description	Expected Results
		0.01 G2/Hz at 12 Hz 0.01 G2/Hz at 100 Hz 0.00001 G2/Hz at 500 Hz nominal of 1.1 Grms 15 min, Z axis Bottom, Top, Left, Right, Front, Back / OF	
SV.4	Vibration Sinusoidal (Non-Operating)	5-500-5 Hz, 0.25 oct/min 0.5 G, one sweep/axis, (Z) only 0.25 G, one sweep/axis, (X, Y) 1 sweep per axis / OF	No permanent system damage and no parts or connectors dislodged.
SV.5	Mechanical Shock (Operating)	See Table 3-15 for items marked with "x" for required test G level and test setup. Total 18x shocks (half-sine)	No permanent system damage, no parts or connectors dislodged and the system stays operational.
SV.6	Mechanical Shock (Non-Operating)	See Table 3-16 for items marked with "x" for required test G level and test setup. Total 6x shocks (trapezoidal)	No permanent system damage and no parts or connectors dislodged.

Table 3-15. Mechanical Shock – Half Sine (Operating)

System Weight (lbs)		3G/11 ms	6G/11 ms	Test Setup
1U/2U	< 70 lbs	--	x	3 axes: $\pm X$, $\pm Y$, $\pm Z$
	> 70 lbs	x	Desired	3 shocks each direction
4U	< 200 lbs	x	Desired	
	> 200 lbs	x	--	
6 U	> 200 lbs	x	--	

Table 3-16. Mechanical Shock – Trapezoidal (Non-operating)

System Weight (lbs)		15G/11 ms	20G/11 ms	30G/11 ms	40G/11 ms	Test Setup
1U/2U	< 70 lbs	--	--	x	Desired	6 sides: Bottom, Top, Left, Right, Front, Back
	> 70 lbs	--	x	Desired	--	6 sides: Bottom, Top, Left, Right, Front, Back
4U	< 200 lbs	--	x	--	--	6 sides: Bottom, Top, Left, Right, Front, Back
	> 200 lbs	x	--	--	--	3 axes: X, Y, Z

System Weight (lbs)	15G/11 ms	20G/11 ms	30G/11 ms	40G/11 ms	Test Setup
					Bottom side down
6 U	> 200 lbs	x	--	--	3 axes: X, Y, Z Bottom side down

Pass or Fail Criteria

Test items in Table 3-14 are completed and passed.

3.10.3 Environmental Reliability Test

Purpose

The purpose of the environmental reliability test is to evaluate the hardware's ability to operate effectively and reliably under various environmental conditions, such as temperature extremes, humidity, and altitude.

Test Procedure

Perform the test items in the following table using the test conditions outlined in the “Test Item Description” column.

Table 3-17. Reliability Test Summary

ID	Subcategory	Test Item Description	Expected Results
R.1	Tray Reliability Pre-Baseline	No device is missing and Partner_MFG_Diag must pass.	The system is stable and passes all tests.
R.2	Tray Reliability Temperature and Humidity (Non-Operating)	1. 25°C, 50% RH for 1 hour 2. -40°C, No Humidity control for 16 hours 3. 70°C, 10% RH for 16 hours 4. 70°C, 90% RH for 16 hours 5. 40°C, 93% RH for 96 hours 6. 25°C, 50% RH for 4 hour > Max Ramp rate : 20°C per hour; 20% RH/hr > Wet vs. Dry, based on product spec	No permanent system damage or degradation
R.3	Tray Reliability Temperature and Humidity (Operating)	1. 25°C, 50% RH for 1 hour 2. 0°C, No Humidity control for 24 hours 3. Max temp ¹ °C, 50% RH for 24 hours 4. 31°C, 85% RH for 24 hours 5. 25°C, 10% RH for 24 hours	No permanent system damage or degradation

ID	Subcategory	Test Item Description	Expected Results
		> Max Ramp1 rate: 20°C per hour; 20% RH/hr	
R.4	Tray Reliability Thermal cycling (Non-Operating)	Ta: 0°C to 100°C 15 min dwell, ramp rate 10°C/min 100 cyc / OF	No permanent system damage
R.5	Tray Reliability Thermal Shock (Non-Operating)	Ta: -20°C to 85°C, 30°C/min, 1 hr dwell 127 min/cyc 100 cyc / OF	No permanent system damage
R.6	Tray Reliability Connector Durability	50 cycles / OF	No permanent system damage or degradation
R.7	Tray Reliability Hard Boot (AC Power ON/OFF) low temperature	1. 0°C for 500 boot cycles 2. 500 cyc / 2F 3. 50% R.H.	No boot failures and no permanent system damage or degradation
R.8	Tray Reliability Hard Boot (AC Power ON/OFF) high temperature	1. Max Temp ¹ °C for 500 boot cycles 2. 500 cyc / 2F 3. 50% R.H.	No boot failures and no permanent system damage or degradation
R.9	Tray Reliability Soft Boot (OS Power ON/OFF) low temperature	1. 0°C for 500 boot cycles, 50% R.H. 2. 500 cyc / 3F 3. 50% R.H.	No boot failures and no permanent system damage or degradation
R.10	Tray Reliability Soft Boot (OS Power ON/OFF) high temperature	1. Max Temp ¹ °C for 500 boot cycles 2. 500 cyc / 3F 3. 50% R.H.	No boot failures and no permanent system damage or degradation
R.12	Tray Reliability Four Corner High Temp and High Voltage	Max Temp ¹ °C, +5% voltage, run diagnostics x1 loop	Systems functions normally with no failures or damage
R.13	Tray Reliability Four Corner High Temp and Low Voltage	Max Temp ¹ °C, -5% voltage, run diagnostics x1 loop	Systems functions normally with no failures or damage
R.14	Tray Reliability Four Corner Low Temp and High Voltage	0°C, +5% for 0.5 hours	Systems functions normally with no failures or damage
R.15	Tray Reliability Four Corner Low Temp and Low Voltage	0°C, -5% for 0.5 hours	Systems functions normally with no failures or damage
R.16	Tray Reliability Temperature and Altitude (Non-Operating)	1. 25°C, for 1 hour 2. -40°C, 40000 ft for 10 hours 3. 70°C, 40000 ft for 10 hours > Ramp rate: not exceed 1°C / min, 50 mbar/min > Wet vs. Dry, based on product specification	No permanent system damage or degradation

ID	Subcategory	Test Item Description	Expected Results
R.17	Tray Reliability Temperature and Altitude (Operating)	1. 5°C, 1,000 ft 2. 25°C, 10,000 ft 3. 5°C, 10,000 ft 4. 5°C, 5,000 ft 5. 25°C, 5,000 ft 6. 30°C, 5,000 ft 7. 30°C, 1,000 ft 8. Max Temp ¹ °C, 1000 ft > 8-hr dwell at each point > Ramp rate: not exceed 1°C/min, 50 mbar/min	No permanent system damage or degradation
R.19	Tray Reliability CMTBF Analysis	1. Telcordia SR-332 Issue 4 2. Method I, Case 1 3. 25°C and Max. Temp °C 4. Ground benign operating environment	Ensure system CMTBF meets expectations and if there are preventable failures those are highlighted
R.20	Tray Reliability DMT	Functional test at 35°C for ~60 days. Tested on 4x trays.	No permanent system damage or degradation
R.25	Tray Reliability Post Baseline	No device is missing and diag must pass	System is stable and passes all tests and performance is equivalent to pretest baseline.
Note: ¹ Max Temp is the max operational and non-operational temperature per product specification.			

Pass or Fail Criteria

The test items in Table 3-17 are completed and passed.

3.10.4 Electromagnetic Compatibility

Purpose

The purpose of electromagnetic compatibility (EMC) testing for server products is to ensure that the servers operate reliably without causing or being affected by electromagnetic interference in their intended environment.

Partners must perform EMC testing according to their intended regulatory standards for electromagnetic emissions and immunity. The following tests can be used for partner reference.

Test Procedure

Perform the test items in the following table according to the government standards outlined in the “Reference Standards” column.

Table 3-18. EMC Tests Summary

ID	Subcategory	Test Item Description	Reference Standards
EM.1	Radiated emissions per standard EN55032	6dB under the class A limit line	EN55032 / FCC CFR 47 Part 15 Subpart B
EM.2	Conducted emissions	6dB under the class A limit line	EN55032 / FCC CFR 47 Part 15 Subpart B
EM.3	Harmonic current emission	Limits for harmonic current emissions (equipment input current ≤ 16 A per phase)	EN 61000-3-2 or EN 61000-3-11 (> 16 A and ≤ 75 A per phase)
EM.4	Voltage fluctuations and flicker	Limitation of voltage fluctuations and flicker in low-voltage supply systems for equipment with rated current ≤ 16 A	EN 61000-3-3 or EN 61000-3-12 (> 16 A and ≤ 75 A per phase)
EM.5	Electro-static Discharge	± 8 kV Contact discharge, ± 15 kV Air discharge Device shows a malfunction but recovers automatically (without user interaction) and then continues to operate normally.	EN61000-4-2
EM.6	Radiated Radio Frequency, Electric Field Immunity	1kHz 80% AM modulation, radiated electromagnetic field of 3 V/m <ul style="list-style-type: none"> > 80 MHz to 1 GHz > 1800 MHz (± 1 %) > 2600 MHz (± 1 %) > 3500 MHz (± 1 %) > 5000 MHz (± 1 %) 	EN61000-4-3
EM.7	Electrical Fast Transient Burst	± 2 kV Mains ± 1 kV signal ports > 3 m	EN 61000-4-4
EM.8	Surge	Test 1.2/50 (8/20) μ s <ul style="list-style-type: none"> > ± 1.2kV differential > ± 2.2kV common 	EN 61000-4-5
EM.9	Radio-Frequency Fields	1 kHz 80% AM modulation <ul style="list-style-type: none"> > 150 kHz to 10 MHz injected level of 3 Vrms > 10 MHz to 30 MHz injected level of 3 to 1 Vrms OPSSIEMC4001 18 June 2021 <ul style="list-style-type: none"> > 30 MHz to 80 MHz injected level of 1 Vrms 	EN61000-4-6
EM.10	Magnetic Fields	Magnetic field of 3A/m at 50Hz	EN61000-4-8
EM.12	Tray Safety Test	CB and UL/cTUVus	IEC 62368-1 ED2 +ED3, UL62368-1 ED3

Pass or Fail Criteria

The test items in Table 3-18 or partner-selected regulatory standards are completed and passed.

Rik Kishnah NVIDIA Confidential Oracle Labs - NVL
1122395 2025-11-28 16:00:27

Chapter 4. L10 Compute Tray System Software

Partners should review the corresponding software collaterals outlined in Table 4-1 and implement the necessary features before starting the compute tray software validation.

Refer to the latest Grace Software Partner Enablement (NVOnline: 1093429) deck for a full list of relevant software collaterals.

Table 4-1. Reference Documentation and Collateral

NVOnline ID	Title	Focus Area
1093429	Grace Software Partner Enablement	All
1099753	Grace Firmware Reference Guide	Boot Firmware
1097474	Grace UEFI External Architecture Specification	Boot Firmware
1110059	SBIOS Requirements for NVIDIA Grace Server Platforms	Boot Firmware
1105630	Grace Platform SBIOS Build Tools and UEFI Reference Code	Boot Firmware
1086146	Grace System PLDM Product Descriptor Record	Boot Firmware
1094659	Grace OpenBMC External Architecture Specification	Baseboard Management
1116996	GB200 NVL Firmware External Architecture Specification	Baseboard Management
1110060	BMC Requirements for NVIDIA Grace Server Platforms	Baseboard Management
1096064	NVIDIA Grace Baseboard Redfish Model and Schema Guide	Baseboard Management
1092300	NVIDIA Data Center Products Telemetry Catalog	Baseboard Management
1030060	SMBUS Post Box Interface (SMBPBI) for NVIDIA Baseboards	Baseboard Management
1099558	Grace Baseboard Firmware Update and Security Guide	Baseboard Management
1090539	Grace OpenBMC Reference Code	Baseboard Management
1098624	Device Ownership Transfer External Architecture Specification	ERoT, DOT, Security
1105290	NVIDIA Device Ownership Transfer User Guide	ERoT, DOT, Security
1109481	NVIDIA SPDM Measurement Block Definition	ERoT, DOT, Security
1109972	MCTP Vendor Defined Messages for CEC1736	ERoT, DOT, Security
1100855	NVIDIA Grace RAS Overview	RAS
1116117	NVIDIA Server RAS Catalog	RAS

NVOnline ID	Title	Focus Area
1115302	NVIDIA CPER Catalog	RAS
1109712	Debug and RAS Guide for NVIDIA Data Center Products	RAS
1116450	NVIDIA Defined CPER Extension to Arm LibCper	RAS

The definitive deliverable for L10 software validation is the successful completion and subsequent submission of the NVSSVT and NVRAS Tool. This ensures a standardized measure of software quality across our partner platforms.

Refer to the Section 1.2.2 “NVSSVT” for more information on running the NVSSVT for software validation.

4.1 System Software Validation Guidelines

Partners are strongly encouraged to review the software requirements documentation to formulate their software test plan. The software areas of interest in this section can serve as a basis for partners to formulate their software test plans.

Partners are recommended to modify or conduct additional testing that may be necessary for their specific use case. For example, partners can develop test cases to validate areas such as the ones in Table 4-2.

Table 4-2. System Software Validation Example

Category	Feature to Check
BMC	Check BMC firmware features against NVIDIA BMC architecture specifications Verify CPER log support Verify POST Code capture Verify time management such as RTC, NTP Check for User Management: LDAP & AD user Device Ownership Transfer (DOT) for Grace CPUs
IPMI	IPMI Standard 2.0- Compliance IPMI Network Management: Static IP, DHCP IPMI SDR (Sensor Data Record), System Event Log (SEL) IPMI User Management- IPMI users and Role Back Access Control IPMI - RMCP+ Support Only IPMI – SOL (serial over lane) feature IPMI Chassis control – power management, PEX boot
Inventory check	Check for server hardware, FRU inventory, firmware and software inventory
Firmware security	TPM function check

Category	Feature to Check
	Verify secure boot support Verify write-protect feature for Host BMC control of the motherboard
Firmware update	Verify motherboard APs and EROTs are capable of firmware upgrade OOB Host BMC firmware update for all APs (CPU, GPU, FPGA, and so on) and EROTs Firmware update rollback – retain previous good images before failed firmware update
SBIOS	Check SBIOS features against NVIDIA SBIOS architecture specifications OS installation via USB, PXE, HTTP boot, virtual media
Redfish Implementation	Verify Redfish API implementation, such as: <ul style="list-style-type: none"> > Redfish Root, Redfish Managers, Redfish LogServices > UEFI settings control by Redfish > System Boot by Redfish > Remote chassis power management by Redfish
Telemetry	Check for in-band and OOB telemetry implementation against the NVIDIA Telemetry Catalog
Server RAS	Verify features against server RAS catalog Verify features NVIDIA CPER catalog Verify EINJ (error injection) response against error catalog
Benchmarks	Test system against performance benchmark suites: <ul style="list-style-type: none"> > nvbandwidth > NCCL > Fuse Multiple Add for Grace CPU > DGEMM > Multichase > OpenSSL > cublasMatMulBnech > IdelLatency > L1L3Latency, and so on

Chapter 5. L11 Server Rack Hardware Validation

This chapter describes the hardware validation items of the L11 server rack.

5.1 Rack Power

This section details the rack power testing and procedures for the GB200 and GB300 NVL systems.

Partners must work with their facility and lab safety personnel when performing rack-level power validation and review the following points before conducting measurements.



Caution: Working with 3-phase AC power can be extremely dangerous. To ensure safety, adhere to the following guidelines:

- > **Qualified Personnel Only:** Ensure that all test setups are verified by a qualified electrician before proceeding.
- > **Personal Protective Equipment (PPE):** When necessary, wear appropriate PPE, including insulated gloves, safety glasses, and protective clothing.
- > **Clear Area:** Keep the test area clear of unnecessary personnel and equipment. Ensure that all non-essential personnel are at a safe distance.
- > **Emergency Procedures:** Familiarize yourself with emergency procedures and ensure that emergency shutdown mechanisms are easily accessible.
- > **Proper Grounding:** Verify that all equipment is properly grounded to prevent electrical shock.
- > **Signage and Barriers:** Use clear signage and physical barriers to mark high voltage areas and restrict access.
- > **Double-Check Connections:** Before powering up, double-check all connections and ensure that they are secure and correctly configured.
- > **Stay Alert:** Always stay alert and focused when working with high voltage equipment. Avoid distractions and never work alone.

5.1.1 Rack Power Startup and Shutdown

Purpose

Verify the server rack power startup and shutdown behavior is within the bus bar power specification.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test conditions

Test under the following input voltage conditions: 200, 208, 220, 240, 277, and 305 VAC.

Test with the following redundancy configurations:

- > All PSUs operational (N+1 per shelf, N+1 per rack)
- > PSUs in non-redundant configuration depending on the rack redundancy model (N+0)

Test Procedure

For each test condition follow these steps:

1. Turn on all PSU AC input at the same time
2. Turn on A-feed group or B-feed group staggered (if an N+N redundancy model) with 1-second, 10-second, 30-second, or 60-second delay between feed group powering.
3. Turn on on-whips 1-by-1 with at least 10-second delay between whips.
4. Measure and record the following parameters for each test condition:
 - a. Startup and shutdown sequence
 - b. DC bus bar voltage
 - c. Vshare bus for power shelves
 - d. AC input current, AC input voltage
 - e. PSC (power shelf controller) event logs
 - f. Monitor power shelf LEDs

Pass or Fail Criteria

- > Bus bar voltage is always within specifications after the first power shelf initiates start-up.
- > Ramp-up rate (10% to 90%) is within 60 ms +/- 10%. No overshoot or ringing.

5.1.2 Rack Power Startup and Shutdown without PSC

Purpose

Verify that the server rack's power startup and shutdown behavior is within the bus bar power specification when one of the power shelves does not have a PSC.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test conditions

Test under the following input voltage conditions: 200, 208, 220, 240, 277, and 305 VAC.

Test with the following redundancy configurations:

- > All PSUs operational (N+1 per shelf, N+1 per rack)
- > PSUs in non-redundant configuration depending on the rack redundancy model (N+0)

Test Procedure

For each test condition follow these steps:

1. Turn on all PSU AC input at the same time
2. Turn on A-feed group or B-feed group staggered (if an N+N redundancy model), without specific delay time, between feed group powering
3. Turn on on-whips 1-by-1 with at least 10-second delay between whips.
4. Measure and record the following parameters for each test condition:
 - a. Startup and shutdown sequence
 - b. DC bus bar voltage
 - c. Vshare bus for power shelves
 - d. AC input current, AC input voltage
 - e. PSC (power shelf controller) event logs
 - f. Monitor power shelf LEDs

Pass or Fail Criteria

- > Bus bar voltage is always within specifications after the first power shelf initiates start-up.
- > Ramp-up rate (10% to 90%) is within 60 ms +/- 10%. No overshoot or ringing.

5.1.3 Rack Power Load Voltage Regulators under Static Load

Purpose

Verify bus bar power delivery and power balancing are stable across static load levels while applying different static loads using test load sleds.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test conditions

Test under the following input voltage conditions: 200, 208, 220, 240, 277, and 305 VAC.

Test with the following static load conditions: 10%, 25%, 50%, 75%, or 100%

Test Procedure

For each test condition follow these steps:

1. Turn on all PSU AC inputs at the same time.
2. Apply static load conditions from the load sleds or electronic loads across different static load conditions.
3. Measure and record the following parameters for each test condition:
 - a. DC bus bar voltage
 - b. Vshare bus for power shelves
 - c. AC input current, AC input voltage
 - d. PSC (power shelf controller) event logs
 - e. Monitor power shelf LEDs

Pass or Fail Criteria

Sharing tolerance for PSUs within common power shelf:

- > +/- 5% (tentative) at 40% -100% load
- > +/- 7% (tentative) at 20% - 30% load
- > +/-10% (tentative) at 10% load

Sharing tolerance for PSUs within common rack:

- > +/-7% (tentative) at 40% -100% load
- > +/- 9% (tentative) at 20% - 30% load
- > +/-12% (tentative) at 10% load

5.1.4 Rack Power Load Voltage Regulators under Dynamic Load

Purpose

Verify bus bar power delivery and power balancing are stable across static load levels, while under dynamic loads using test load sleds.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test conditions

Test under the following input voltage conditions: 200, 208, 220, 240, 277, and 305 VAC.

Test with the following load conditions:

- > Sweep from 10% - 90% load condition, with 50 ms-ON and 50 ms-OFF
- > Sweep from 30% - 100% load condition, with 50 ms-ON and 50 ms-OFF
- > Test to power shelf peak power rating with 50 ms-ON and 50 ms-OFF

Test with the following slew rates:

- > 1 A/μs
- > 6 A/μs
- > 12 A/μs

Test Procedure

1. Apply the input voltage condition VAC
2. Program the electronic load to the designated slew rate (1 A/μs, 6 A/μs, or 12 A/μs)
3. Program the electronic load to sweep through each load condition with 50 ms-ON and 50 ms OFF pulse
4. Measure and record the following parameters for each test condition:
 - a. DC bus bar voltage
 - b. Vshare bus for power shelves
 - c. AC input current, AC input voltage
 - d. PSC (power shelf controller) event logs
 - e. Monitor power shelf LEDs

Pass or Fail Criteria

Sharing tolerance for PSUs within common power shelf:

- > +/- 5% (tentative) at 40% -100% load
- > +/- 7% (tentative) at 20% -30% load
- > +/-10% (tentative) at 10% load

Sharing tolerance for PSUs within common rack:

- > +/-7% (tentative) at 40% -100% load
- > +/- 9% (tentative) at 20% -30% load
- > +/-12% (tentative) at 10% load

5.1.5 Rack Power Load Hot Swap PSU

Purpose

Verify that PSU modules can successfully be hot swapped in a power shelf without interrupting the server rack system.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test conditions

Test under the following input voltage conditions: 240, 277, and 305 VAC.

For racks with N+N power redundancy, test with only N feeds.

Test Procedure

1. Turn on the electronic load, and load the rack power system with 100% load
2. Hot swap PSU modules one at a time inside a power shelf while the rack is operational
3. Monitor and record PSU LED status and PSC status telemetry after hot swap

Pass or Fail Criteria

- > PSU modules can successfully be hot swapped in a power shelf without interrupting the system.
- > PSU and PSC should continue to regulate the bus bar voltage within range, with real-time current sharing, no OVP, UVP, OCP, or any other faults to be triggered due to interrupt or hiccup on the bus bar voltage.
- > No fault is registered in the PSU and PSC telemetry status.
- > All LEDs are showing the correct status.

5.1.6 Rack Power Load Hot Swap PSC

Purpose

Verify that PSC modules can successfully be hot swapped in a power shelf without interrupting the server rack system.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test conditions

Test under the following input voltage conditions: 240 VAC.

Test Procedure

1. Turn on the electronic load, and load the rack power system with 100% load
2. Hot swap the PSC module inside a power shelf while the rack is operational
3. Monitor and record neighboring PSU LED status

Pass or Fail Criteria

- > PSU and PSC should continue to regulate the bus bar voltage within range, with real-time current sharing, no OVP, UVP, OCP, or any other faults to be triggered due to interrupt or hiccup on the bus bar voltage.
- > No fault is registered in the PSU and PSC telemetry status.
- > All power shelf LEDs are showing the correct status.

5.1.7 Rack Power Fault Recovery

Purpose

Verify that power shelf protection and fault recovery features (OCP, OTP, brownout, and OVP) work as expected.

Prerequisite

Partners can use test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test Conditions

Test under the following input voltage conditions: 240 VAC.

Test with the following load conditions:

- > 10% - 90% dynamic load
- > 100% static load

Test Procedure

1. OCP: While the rack is running at 100% static load, remove PSUs one by one until hitting OCP
2. OTP: Use thermal chamber, test with slow thermal ramp up to power shelf maximum rating. If a thermal chamber is not available, block airflow to the power shelf until OTP.
3. Brownout and Brown-in: Ramp the input voltage down until hitting brownout UVLO and PSU shuts down, then ramp voltage back up until brown-in recovery. Verify the recovery feature is still in place for slow ramp (lasting several minutes) and fast ramp (lasting several seconds).
4. OVP: Ramp voltage up to power shelf OVP voltage after hitting fault reduce voltage. Verify the protection feature is still in place for slow ramp (lasting several minutes) and fast ramp (lasting several seconds).
5. For each power fault event, check for PSC event records. Verify the fault records are reported correctly.
6. Verify system can operate normally after the system reset and the faults are cleared.

Pass or Fail Criteria

- > Bus bar power delivery should stay within its acceptable specification range until it turns off.
- > PSC should report faults as expected.
- > System operates normally, after faults are cleared and system is reset.

5.1.8 Rack Power AC Apparent Power


Purpose

The Electrical Design Peak Point (EDPp) testing aims to measure the peak input power within a near-instantaneous timescale, then calculate AC apparent power based on the moving RMS voltage (based on one 60Hz AC cycle).

Peak input power occurs with high transient load, such as the pulse power workload in the Partner Diagnostics.

L11 rack level EDPp test involves measuring input AC power, optional DC power and optional iShare signal. Two 8-channel oscilloscopes might be required to probe AC voltage and current and optional iShare or second power shelf AC input power. The following figure is a block diagram of the test setup.

Figure 5-1. L11 Power Measurement Block Diagram



Assumptions and Estimates

- > The efficiency, power factor, and power sharing among all power shelves are roughly the same.
- > The total L11 rack-level AC input power can be estimated as 4x (or 6x) that of a single power shelf.

Required Test Equipment

- > 1x 8-channel oscilloscopes (for example, Tektronix 5 or 6 Series MSO B). A second 8-channel oscilloscope is optional for measuring the iShare and second power shelf input power.
- > Optional 1x coaxial cable (for synchronizing oscilloscopes together).
- > 4x current probes (for example, Tektronix TCP0150 current probe); 7x current probes are optional for measuring second power shelf input power.
- > 3x high-voltage differential probes (for example, Tektronix TMDP0200 High-Voltage Differential Probe); 6x high-voltage differential probes are optional for measuring second power shelf input power.
- > 1x low voltage differential voltage probe (for example, Tektronix TDP1500 Differential Probe).
- > 1x passive voltage probe (for example, Tektronix TP1000 Passive Voltage Probe).
- > 1x sacrificial AC power whips; 2x sacrificial AC power whips are optional for measuring input power on two power shelves.



Caution:

- > DO NOT use probe ground on the AC input unless approved by a specialist familiar with the facility's AC setup at the partner site.
- > High voltage differential voltage probes, such as the Tektronix TMDP0200, should be used to probe the live AC input voltage. Differential voltage probes are used to cancel out noise on the AC network.
- > If passive probes were used to measure the hot wire compared to ground, then the oscilloscope must be isolated from the AC network by power of the scope using battery or isolating transformer.

Modify AC Power Whip for AC Power Probing

On the AC power cord, perform the following modifications:

1. Remove approximately 15 inches of the outer rubber insulator to reveal individual insulated conductors.
2. On the black, red, orange (hot), and white (neutral) wires, remove about 1/8-inch of insulation to expose the conductors.
3. Attach the positive lead (red) of a high-voltage differential probe to the black (hot) wire, and the negative lead (black) to the neutral (white) wire.
4. Apply Kapton tape around the probes and exposed wires.
5. Place 3x current probes and apply second Kapton tape around the probes to secure all the current probes and voltage probing leads.

Figure 5-2. Power Whip Wiring Diagram





Figure 5-3. Current Probes and Voltage Probes Setup and Power Whip

Prepare Compute Tray PDB for DC Power Probing (Optional)

1. (Optional) Open the compute cover and add voltage probing leads and twisted pair wires to the PDB.
2. (Optional) Place the current probe to the wires from the bus bar connectors to the PDB.



3. (Optional) Customize the white Corrugated Twinwall Plastic to cover the top of the compute tray while leaving an opening for the current probe.



- (Optional) Install the reworked compute tray back to the top tray position

Connect AC Probes

Do the following per power shelf:

1. Verify the power whip top box is off.
2. Attach a modified AC power whip to the power shelf.
3. Reconnect the differential voltage probe heads to the main part of the probe.
4. Attach a current probe around the exposed black (hot) wire (not around the isolated bundle), with the arrow on the probe pointing towards the system.
5. Connect the current probe to the scope.
6. While no voltage and current in the DUT whip, conduct current probe degauss auto-zero and optional scope compensation (SPC).


Figure 5-4. Connected Power Cable and Current Probe Attachments Example



Setup the Oscilloscope (Optional for the Second Oscilloscope)

1. (Optional) Place the two scopes on carts adjacent to the system.
2. (Optional) Connect the coaxial cable to the “Aux Out” port on the primary scope to the “Ref In” port on the secondary scope.
3. (Optional) On the primary scope’s toolbar, select Utility → I/O and use the “Reference Clock” option under “AUX Out Signal.”


4. (Optional) On the secondary scope, open the acquisition menu and select “External (10 MHz)” under “Timebase Reference Source.”




Note: If using 2x 4-channel scopes, two additional requirements must be met:

- > The scopes' sampling clocks need to be synchronized through wiring and configured according to each scope's manual.
- > Each scope should dedicate one channel to measure DC voltage, allowing for the calculation of the time offset between the two scopes.

5. Connect voltage and current probes to the scopes.
6. On the scopes, configure the following sample rate and record length. The horizontal scale could be set at 200 second/div to obtain the max sampling duration of 2000-seconds.



7. Channel setup:
 - a. 6x channels for 3-phase AC input voltage and current.
 - b. 2x channels for DC bus bar voltage and current.
 - c. All 8x channels must be synchronized for transient power analysis. An 8x channel scope should be acquired or leased.
8. On the oscilloscope, add labels for each channel and set up the scale and position. See **Section 6.2 “Input EDPp Post-Processing Guideline”** for additional information.



Setting up the Power Pulse Diag Workload

Use a remote server to run the L11 Partner Diagnostics power pulse diagnostics. Run the CPU and GPU power pulse stress workload for 15 minutes.

Data Processing and Interpreting Results

1. Monitor and capture the waveforms for AC voltage current, optional DC voltage, and system power.
2. Perform power analysis on the captured waveform for the moving average and apparent power. See **Section 6.2 “Input EDPp Post-Processing Guideline”** for additional information.

Pass or Fail Criteria

Verify the maximum apparent power is within the specification listed in the *NVIDIA GB200 and GB300 NVL72 Rack System Specifications* (NVOnline: 1117886 and 1126548).

5.1.9 Rack Power Noise

Purpose

Verify that the power shelf output voltage is within maximum ripple and noise. Maximum voltage noise should be less than 5.5V peak-to-peak under the load frequencies.

Prerequisite

Partners must use a fully populated rack system for this test.

Test Conditions

Test under the following input voltage conditions: 208, 240, and 277 VAC.

Test Procedure

1. Run CPU and GPU power pulse stress workload from the GB200 and GB300 NVL72 L11 Partner Manufacturing Diagnostics.
2. Monitor and capture the waveforms for the power shelf output to the entire rack using an oscilloscope with the highest sampling rate allowed.
3. Measure the DC bus bar voltage (V_{in}) peak-to-peak value.
4. Monitor PSC event logs for any faults or warnings.

Pass or Fail Criteria

Verify that the maximum DC bus bar voltage (V_{in}) peak-to-peak value is less than 5.5V.

5.1.10 Rack Power Firmware Update

Purpose

Verify that the power shelf PSUs and PSC can successfully perform firmware updates and firmware downgrades.

Prerequisite

Partners can test without any compute tray or switch tray.

Test Conditions

- > Test under the following input voltage conditions: 240 VAC.
- > Loading: 100% of N+0 rating. If N+N system, then operate with a single feed while testing.

Test Procedure

1. Upgrade or downgrade a single PSU at a time. Verify that each PSU firmware can be updated successfully.
2. Upgrade or downgrade 2x PSUs at a time. Verify that both PSUs have the correct firmware flashed
3. Upgrade or downgrade PSC one at a time. Verify both primary and secondary firmware flashed correctly.

Pass or Fail Criteria

PSUs and PSCs should upgrade and downgrade successfully without failures.

5.1.11 PSC Reboot Cycles

Purpose

Verify that the PSC (power supply controller) reboot cycle does not affect power delivery.

Prerequisite

Partners can utilize test load sleds or electronic loads to draw power from the power shelf, instead of assembling the full server rack system.

Test Conditions

- > Test under the following input voltage conditions: 240 VAC.
- > Loading: 100% of N+0 rating. If N+N system, then operate with a single feed while testing.

Test Procedure

1. Reboot the PSC one at a time.
2. During reboot, monitor the DC bus bar voltage and verify that the bus bar power remains stable during and after each reboot.
3. Read PSC status telemetry after each reboot. Verify there are no errors.

Pass or Fail Criteria

Bus bar power delivery remains stable during and after each PSC reboot.

5.1.12 Rack Power Factor

Purpose

Power factor measures how efficiently the power supply converts electrical power into usable power for the server. This test is to measure the power factor of the rack power supply under various load conditions.

Prerequisite

Partners must use a fully populated rack system for this test.

Test Conditions

Test with the following load conditions:

- > Static light load
- > Static heavy load
- > Dynamic load at low frequency (CPU and GPU power pulse stress at low frequency)

Test Procedure

1. Run the server rack under each load condition: static light load, static heavy load, and dynamic load at low frequency.
2. Measure the 3-phase AC voltage and current (sampling rate 100 μ s/pt) using an oscilloscope
3. Perform power factor calculation with 1, 2, 3, 5, 10, or 60 cycles (60 Hz per cycle). Power factor calculation should be done with the power drawn by the server divided by the product of the 3-phase voltage and current

Pass or Fail Criteria

- > Power factor for static light load should be greater than 0.90.
- > Power factor for static heavy load should be greater than 0.95.
- > Power factor for dynamic load at low frequency should be greater than 0.85.

5.2 L11 Environmental, Reliability

NVIDIA recognizes the diversity of potential use cases that system partners may encounter. The following test lists are the guidance from NVIDIA for the areas concerning environmental factors, reliability, and robustness.

Partners are responsible for validating the system packaging, reliability, and environmental testing to meet their target deployment.

Partners are recommended to modify or conduct additional testing that may be necessary for their specific use case and ensure that all potential scenarios are addressed appropriately.

5.2.1 L11 Packaging

Purpose

The purpose of performing package testing is to ensure that the packaged rack system can withstand the physical stress it may encounter during transportation, storage, and handling.

Test Procedure

Partners should test to the industrial test standards of ISTA. Perform the test items in the following table using the standards highlighted in the “Reference” column.

Table 5-1. L11 Packaging Test Summary

ID	Subcategory	Test Item Description	Test Procedure
RPK.1	Package/Product Visual Inspection and Product Functional PRE-Test	Run functional test on the product using the latest manufacturing diagnostic. Perform visual inspection and record all noted cosmetic observations	Visual inspection and MFG Diagnostics

ID	Subcategory	Test Item Description	Test Procedure
RPK.2	Atmospheric Pre-Conditioning	Packaged product shall be preconditioned to laboratory ambient temperature and humidity for minimum of 12 hours	ISTA 3B, Block #1
RPK.3	Atmospheric Conditioning (Required only for non rigid containers)	[Hot, Humid] then [Extreme Heat, Moderate RH] [38°C, 85% RH for 72 hours] then [60°C, 30% RH for 6 hours]	ISTA 3B, Block #1
RPK.4	Tip Test	Test up to 22-degree angle, without letting fall. Report on center of gravity tilt angle. If packaged product fails this test, DO NOT let it fall to the floor. Gently return the product to upright position and note failure. Continue testing.	ISTA 3B, Block #2
RPK.5	Shock – Rotational Drop	Drop height 6 in (150 mm) for packaged products weighing 500 lb (230 Kg) or more	ISTA 3B, Block #5
RPK.6	Shock – Incline or Horizontal Impact	Impact velocity 48 in/sec (1.2 m/sec) minimum or 3 in (76 mm) drops	ISTA 3B, Block #6
RPK.7	Truck Vibration - Random with top load	Overall 0.54 Grms, 120 minutes	ISTA 3B, Block #9
RPK.8	Air Vibration - Random	Combination of High (0.29 Grms), Medium (0.22 Grms) and Low (0.16 Grms) air profile; 120 minutes	ASTM D4169-23, section 12.4.2.2
RPK.9	Concentrated Impact (Required only for non rigid containers)	Free-fall, or guided fall drop	ISTA 3B, Block #10
RPK.10	Fork Lift Handling (Required only for non rigid containers)	Flat Push and Rotate Tests, Elevated Push and Pull Tests, Elevated Rotate Tests, Load stability test over a handling course.	ISTA 3B, Block #15
RPK.11	Shock – Rotational Drop	Drop height 6 in (150 mm) for packaged products weighing 500 lb (230 Kg) or more	ISTA 3B, Block #13

Pass or Fail Criteria

Test items in Table 5-1 are completed, such that the product did not sustain any damage and met the ISTA requirements.

- > Product is damage-free; no structural damage including no detached, loose, fractured, or deformed material parts.
- > Product cosmetic areas are not degraded beyond manufacturing or final acceptance criteria. Cosmetic damage is any abnormality that makes the product unacceptable to the customer.
- > No conductive particles (wire, connectors, and so on) should be exposed because of the testing.
- > The product should meet all manufacturing specifications and tolerances after testing

- > All the product electrical and software functions perform to specification

5.2.2 L11 Shock and Vibration Test

Purpose

The purpose of shock and vibration testing is to ensure that the rack system can withstand physical stress during transportation, handling, and operation. The testing simulates the effects of sudden impacts and continuous or repetitive movements to verify the compute tray's durability and functionality.

Test Procedure

Perform the test items in the following table using the standards highlighted in the Reference column.

Table 5-2. L11 Shock and Vibration Test Summary

ID	Subcategory	Test Item Description	Expected Results
RSV.1	Rack SV Vibration Random Operating	Freq Hz / PSD level (G ² /Hz) / Slope (dB/oct) 5 - 10 / - / +12 10 - 50 / 0.0002 / - 50 - 100 / - / +12 30 mins / per axes ; 3 axes 0.108 Grms	No permanent system damage, no parts or connectors dislodged, and system stays operational
RSV.6	Rack SV Handling Obstacle	Roll over a 4mm vertical step with each caster independently at 0.8m/s, 5 times each	This can be done successfully without damage or needing special equipment and meets specification
RSV.7	Rack SV Handling Gap	Traverse 25.4mm wide gap in the floor at 0.5m/s, 5 times	This can be done successfully without damage or needing special equipment and meets specification
RSV.8	Rack SV Handling Ramp	Transition a 5-degree ramp both up and down. From a flat surface, traverse a 5 degree ramp up to an elevated flat surface. From an elevated flat surface, traverse down a 5-degree ramp down to a flat surface.	This can be done successfully without damage or needing special equipment and meets specification
RSV.9	Rack SV Handling Roll-off	19mm, 5 times per direction (with front leading and then with rear leading)	This can be done successfully without damage or needing special equipment and meets specification
RSV.10	Rack SV Handling Distance Roll	Roll 800m on a concrete floor at 0.8m/s, without stopping for prescribed distance. After completing the four tests	This can be done successfully without

ID	Subcategory	Test Item Description	Expected Results
		above, the force (kgw) required to push the rack from a non-moving position along a smooth, flat cement floor SHALL be less than 5% the total combined weight (kgw) of the rack and IT Gear.	damage or needing special equipment
RSV.11	Rack SV Handling Tilt	Tilted to an angle of 10 degrees from its normal upright position and held in this position for 1 minute. Repeated for all four sides (front, back, left, right). (1) Test with maximum payload, evenly distributed in rack. Add-on stabilizers MAY be used to meet this requirement for rack at max payload. (2) base rack with no payload SHALL also pass with no stabilizer	This can be done successfully without damage and meets specification.
RSV.12	Rack SV Handling Leveling	Leveling feet SHALL be raised and lowered 3 cycles individually to raise rack to 15 mm off the floor until all 4 are raised. Start with front left, then rear right, rear left, and finally front left. Lower in reverse order. Repeat for 3 cycles.	This can be done successfully without damage and meets specification.
RSV.13	Rack SV Handling Lateral Load	While in its normal position on a flat surface, with casters rotated towards the surface, a force equal to 20 percent of the weight of the fully loaded enclosure system, but not more than 250 N (56.2 lbf), is applied in any direction except upwards, at a height not exceeding 2 m (78.74 in) from the floor. The force is applied to the front, back, and each side of the system, each for 1 minute.	This can be done successfully without damage or falling over.
RSV.14	Rack NVLink Traffic + Stress Test after SV	Run the L11 Diag traffic test on the rack	Relevant test workload is passing.

Pass or Fail Criteria

Test items in Table 5-2 are completed and passed.

5.2.3 L11 Environmental Reliability Test

Purpose

The purpose of the environmental reliability test is to evaluate the hardware's ability to operate effectively and reliably under various environmental conditions, such as temperature extremes, humidity, and altitude.

Test Procedure

Perform the test items in the following table using the test conditions outlined in the table.

Table 5-3. L11 Reliability Test Summary

ID	Subcategory	Test Item Description	Expected Results
RL.1	Rack Reliability Pre Baseline	No device missing and diag must pass.	The system is stable and passes all tests.
RL.2	Rack Reliability Temperature and Humidity (Non-operating)	1. 25°C, 50% RH for 1 hour 2. -40°C, No Humidity control for 16 hours 3. 70°C, 5% RH for 16 hours 4. 70°C, 95% RH for 16 hours 5. 40°C, 93% RH for 96 hours 6. 25°C, 50% RH for 4 hour 7. Max Ramp rate : 20°C per hour; 20% RH/hr	No permanent system damage or degradation.
RL.3	Rack Reliability Temperature and Humidity (Operating)	1. 25°C, 50% RH for 1 hour 2. 0°C, No Humidity control for 24 hours 3. Max Temp°C, 50% RH for 24 hours 4. 31°C, 85% RH for 24 hours 5. 25°C, 10% RH for 24 hours 6. Max Ramp rate: 10°C per hour; 10% RH/hr	No permanent system damage or degradation. Liquid cooled: max temperature per design spec (condensation must be prevented).
RL.4	Rack Reliability Connector Durability	50 cycles / OF Test system connectors: cable cartridge, PSUs, and network ports	No permanent system damage or degradation
RL.5	Rack Reliability Manifold Mate Durability	50 cycles / OF Test trays and manifold connection	No connector damage or leakage
RL.6	Rack Reliability Hard Boot low temperature	1. 0°C for 500 power shelf AC cycles 2. 500 cyc / 2F (Condensation must be prevented)	No boot failures and no permanent system damage or degradation.
RL.7	Rack Reliability Hard Boot high temperature	1. Max Temp °C, 50% RH for 500 power shelf AC cycles 2. 500 cyc / 2F	No boot failures and no permanent system damage or degradation.

ID	Subcategory	Test Item Description	Expected Results
RL.13	Rack Reliability Soft Boot (OS reboot) low temp	1. 0°C for 500 boot cycles 2. 500 cyc / 3F (Condensation must be prevented)	
RL.14	Rack Reliability Soft Boot (OS reboot) high temperature	1. Max Temp °C, 50% RH for 500 boot cycles 2. 500 cyc / 3F	
RL.8	Rack Reliability Soak and Boot low temp	1. 25°C for 3000 power shelf boot cycles 2. 3000 cyc / 6F	No boot failures and no permanent system damage or degradation.
RL.10	Rack Reliability CMTBF Analysis	Telcordia SR-332 Issue 4 Method I, Case 1 25°C and max temp °C Ground Benign operating environment	Ensure system CMTBF meets expectations, and if there are preventable failures, those are highlighted.
RL.12	Rack Reliability Post Baseline	No device missing and diag must pass.	The system is stable and passes all tests, and performance is equivalent to the pretest baseline.

Pass or Fail Criteria

The test items in Table 5-3 are completed and passed.


Chapter 6. Appendix 1: Oscilloscope Acquisition Modes for EDPp Measurements

6.1 Moving Average Measurement using Oscilloscope HiRes Mode

When using the “High Res” acquisition for input EDPp measurement, the oscilloscope acquisition mode to “High Res” or “Hi Res” mode.

The “High Res” mode in most oscilloscopes oversamples and calculates the average of all the samples for each acquisition interval. Input EDPp current and power measurements can be performed via the “HiRes” mode, as this mode performs a boxcar averaging on the samples within an acquisition interval.

Figure 6-1. Acquisition Mode



For example, a 5 kS/s interval equates to a 200 μ s/pt moving average timescale, and 10 kS/s interval equates to a 400 μ s/pt moving average timescale.

Oscilloscope settings for 200 μ s timescale moving average measurement

- > **X-Axis (suggested):** 20 ms/division or custom to capture the transient
- > **Y-Axis (suggested):** 5 A/division or 10 A/division based on the maximum expected current transient level
- > **Trigger:** Set as edge trigger. First, determine the “idle” current level using AUTO trigger. A good edge trigger level will be between the idle limit and the expected average power capping limit to capture the initial spike.
- > **Persistence mode:** Off
- > **Vertical setting:** Channel 1/2/3/4
 - Set termination to 50 ohm and bandwidth to 20 MHz to reduce noise
- > **Horizontal/ Acquisition tab:** Acquisition
 - Set acquisition mode to “High Res,” set Fast Acquisition mode to Off, set Roll Mode to Off, and Sampling Mode to Real-Time.
- > **“HiRes” Averaging:** 200 μ s/pt

The following image shows an example oscilloscope setting for a 200 μ s moving average timescale measurement.

Figure 6-2. Oscilloscope Setting 200 μ s Moving Average Example

6.2 Input EDPp Post-Processing Guideline

When using the post-processing technique for input EDPp calculation, the oscilloscope acquisition mode to sample mode. When performing input EDPp moving average analysis on captured oscilloscope waveform files (*.wfm), the following procedures can be implemented programmatically for input EDPp analysis.

1. Waveform Data Loading and Processing:

- Load waveform data from multiple .wfm files, representing current and voltage waveforms for both DC and AC.
- Calculate the start and stop times for data extraction based on user-defined stop/start parameters. For example,
- Set up scope sampling rates, horizontal/vertical scales, and other parameters required for processing the waveform data. For example, a good sampling rate for input EDPp analysis is 100 μ s/pt with a total record length of 1500 seconds (150 second per horizontal division). A sampling rate of 100 μ s/pt means that the sampling frequency is 10,000 samples per second. As a result, the moving average window and the number of samples can be determined by the following formulas:

$$\text{Scope sampling frequency} = \frac{1}{\text{Recommended Scope Sampling Rate}}$$

$$\text{Number of samples per window} = \text{Moving average window (sec)} * \text{Sampling Frequency (samples/sec)}$$

Table 6-1. Input EDPp and Samples per Window in Sample Mode

Timescale	Moving Average Window	Scope Sampling Rate	Scope Sampling Frequency (Hz)	Number of Samples per Window
Input EDPc	1 second	100 μ s/pt	10,000 Hz	10,000
Input EDPp1	50 ms	100 μ s/pt	10,000 Hz	500
Input EDPp1	50 ms	40 μ s/pt	25,000 Hz	1250
Input EDPp2	400 μ s	100 μ s/pt	10,000 Hz	4
Other	20 ms	100 μ s/pt	10,000 Hz	200

2. Data Extraction and Scaling:

- a. Extracts specific data segments based on calculated start times, scales, and offsets.
- b. Processes each loaded waveform for each channel (current_ch1, current_ch2, voltage_ch1, and so on) to fit within the desired time span and resolution.

3. Instantaneous Power Calculation:

- a. Computes instantaneous AC power for each waveform by multiplying voltage and current measured on input AC lines (for example, Instantaneous AC power = AC Voltage * AC Current).
- b. Calculates the total instantaneous AC power by summing all individual power values from each phase.
- c. Computes instantaneous DC power from DC voltage and current data.

4. AC Apparent Power Analysis for AC Power and Peak Calculations:

- a. Calculates the apparent power (RMS voltage multiplied by RMS current) for each AC voltage/ current channel and stores its value.
- b. Determines the maximum apparent power over 1x AC cycle (60 Hz) for peak apparent power analysis.

5. DC Power Analysis with Input EDPp Moving Average Windows:

- a. For DC power analysis, performs moving average input EDPp calculation for DC voltage and currents over each EDP time intervals (400 μ s, 50 ms, 1 second).
- b. On the captured waveform values, perform a sliding window of samples, and perform averaging across all the values. Refer to Table 6-1. A simple moving average algorithm example can be implemented as follows:

```
# Define the window size for the moving average
window_size = 500

# Initialize an empty list to store the moving averages
moving_average = []

# Calculate the moving average manually
for i in range(len(data) - window_size + 1):
    window = data[i:i + window_size]
    window_average = np.mean(window)
    moving_average.append(window_average)

# Convert the list to a numpy array
moving_average = np.array(moving_average)
```

- c. DC input EDPp values should be less than the value provided in the product specification.

6. Plotting and data visualization:

- a. Creates a figure with multiple subplots, each showing data like apparent power and DC power over time.

- b. Uses the duty cycle and frequency parameters to title the plots, showing system information.
 - c. Provides a visualization of apparent power across multiple power supply units, a DC power plot, and related data.
7. **Summary Calculations:**
- a. Finds the peak-to-peak voltage and current for DC power and the maximum values for apparent power and moving averages of DC power.

Rik Kishnah NVIDIA Confidential Oracle Labs - NVL
1122395 2025-11-28 16:00:27

Chapter 7. Appendix 2: Validation Leverage Guidance for GB300 NVL72 Systems

This chapter outlines the test items that can be leveraged from the GB200 NVL72 PVP Test plan as part of the overall GB300 NVL72 qualification. If partners have performed the full PVP validation on the GB200 NVL72 system, then some of the test items can be leveraged from the GB200 and deemed as “Optional” as part of the GB300 NVL72 qualification.

As part of the PVP leverage guidance, a spreadsheet with a list of PVP test items that can be leveraged from the GB200 NVL72 PVP is attached to this validation guide.

The attached file name is “GB_NVL72_PVP_Validation_Leverage_Guidance.nvzip.” Download the .nvzip file to the local directory, rename the file to a .zip file, and unzip the file to extract the contents. See Section 1.4 for downloading details.

Notice

This document is provided for information purposes only and shall not be regarded as a warranty of a certain functionality, condition, or quality of a product. NVIDIA Corporation ("NVIDIA") makes no representations or warranties, expressed or implied, as to the accuracy or completeness of the information contained in this document and assumes no responsibility for any errors contained herein. NVIDIA shall have no liability for the consequences or use of such information or for any infringement of patents or other rights of third parties that may result from its use. This document is not a commitment to develop, release, or deliver any Material (defined below), code, or functionality.

NVIDIA reserves the right to make corrections, modifications, enhancements, improvements, and any other changes to this document, at any time without notice.

Customer should obtain the latest relevant information before placing orders and should verify that such information is current and complete.

NVIDIA products are sold subject to the NVIDIA standard terms and conditions of sale supplied at the time of order acknowledgement, unless otherwise agreed in an individual sales agreement signed by authorized representatives of NVIDIA and customer ("Terms of Sale"). NVIDIA hereby expressly objects to applying any customer general terms and conditions with regards to the purchase of the NVIDIA product referenced in this document. No contractual obligations are formed either directly or indirectly by this document.

NVIDIA products are not designed, authorized, or warranted to be suitable for use in medical, military, aircraft, space, or life support equipment, nor in applications where failure or malfunction of the NVIDIA product can reasonably be expected to result in personal injury, death, or property or environmental damage. NVIDIA accepts no liability for inclusion and/or use of NVIDIA products in such equipment or applications and therefore such inclusion and/or use is at customer's own risk.

NVIDIA makes no representation or warranty that products based on this document will be suitable for any specified use. Testing of all parameters of each product is not necessarily performed by NVIDIA. It is customer's sole responsibility to evaluate and determine the applicability of any information contained in this document, ensure the product is suitable and fit for the application planned by customer, and perform the necessary testing for the application in order to avoid a default of the application or the product. Weaknesses in customer's product designs may affect the quality and reliability of the NVIDIA product and may result in additional or different conditions and/or requirements beyond those contained in this document. NVIDIA accepts no liability related to any default, damage, costs, or problem which may be based on or attributable to: (i) the use of the NVIDIA product in any manner that is contrary to this document or (ii) customer product designs.

No license, either expressed or implied, is granted under any NVIDIA patent right, copyright, or other NVIDIA intellectual property right under this document. Information published by NVIDIA regarding third-party products or services does not constitute a license from NVIDIA to use such products or services or a warranty or endorsement thereof. Use of such information may require a license from a third party under the patents or other intellectual property rights of the third party, or a license from NVIDIA under the patents or other intellectual property rights of NVIDIA.

Reproduction of information in this document is permissible only if approved in advance by NVIDIA in writing, reproduced without alteration and in full compliance with all applicable export laws and regulations, and accompanied by all associated conditions, limitations, and notices.

THIS DOCUMENT AND ALL NVIDIA DESIGN SPECIFICATIONS, REFERENCE BOARDS, FILES, DRAWINGS, DIAGNOSTICS, LISTS, AND OTHER DOCUMENTS (TOGETHER AND SEPARATELY, "MATERIALS") ARE BEING PROVIDED "AS IS." NVIDIA MAKES NO WARRANTIES, EXPRESSED, IMPLIED, STATUTORY, OR OTHERWISE WITH RESPECT TO THE MATERIALS, AND EXPRESSLY DISCLAIMS ALL IMPLIED WARRANTIES OF NON-INFRINGEMENT, MERCHANTABILITY, AND FITNESS FOR A PARTICULAR PURPOSE. TO THE EXTENT NOT PROHIBITED BY LAW, IN NO EVENT WILL NVIDIA BE LIABLE FOR ANY DAMAGES, INCLUDING WITHOUT LIMITATION ANY DIRECT, INDIRECT, SPECIAL, INCIDENTAL, PUNITIVE, OR CONSEQUENTIAL DAMAGES, HOWEVER CAUSED AND REGARDLESS OF THE THEORY OF LIABILITY, ARISING OUT OF ANY USE OF THIS DOCUMENT, EVEN IF NVIDIA HAS BEEN ADVISED OF THE POSSIBILITY OF SUCH DAMAGES. Notwithstanding any damages that customer might incur for any reason whatsoever, NVIDIA's aggregate and cumulative liability towards customer for the products described herein shall be limited in accordance with the Terms of Sale for the product.

Trademarks

NVIDIA, the NVIDIA logo, BlueField, ConnectX, NVIDIA Grace, NVIDIA MGX, and NVLink are trademarks and/or registered trademarks of NVIDIA Corporation in the U.S. and other countries. Other company and product names may be trademarks of the respective companies with which they are associated.

Arm

Arm, AMBA, and ARM Powered are registered trademarks of Arm Limited. Cortex, MPCore, and Mali are trademarks of Arm Limited. All other brands or product names are the property of their respective holders. "Arm" is used to represent ARM Holdings plc; its operating company Arm Limited; and the regional subsidiaries Arm Inc.; Arm KK; Arm Korea Limited.; Arm Taiwan Limited; Arm France SAS; Arm Consulting (Shanghai) Co. Ltd.; Arm Germany GmbH; Arm Embedded Technologies Pvt. Ltd.; Arm Norway, AS, and Arm Sweden AB.

Copyright

© 2024, 2025 NVIDIA Corporation. All rights reserved.